3.7 PLANT SYSTEMS

3.7.8 Essential Service Water (SX) System

- LCO 3.7.8 The following SX trains shall be OPERABLE:
 - Two unit-specific SX trains; and a.
 - One opposite-unit SX train for unit-specific support. b.

APPLICABILITY: MODES 1, 2, 3, and 4.

ACTIONS

| CONDITION | REQUIRED ACTION | COMPLETION TIME |
|---|---|-----------------|
| ANOTES Not applicable to Unit 1 during replacement of the SX suction isolation valves during Unit 2 Refueling 11 while Unit 2 is in MODE 5, 6, or defueled. | A.1 1. Enter applicable Conditions and Required Actions of LCO 3.8.1, "AC Sources- Operating," for Emergency Diesel Generator made inoperable by SX. | |
| One unit-specific SX train inoperable. | 2. Enter applicable Conditions and Required Actions of LCO 3.4.6, "RCS Loops- MODE 4," for Residual Heat Removal loops made inoperable by SX. | |
| | Restore unit-specific SX train to OPERABLE status. | 72 hours |
| | · · · · · · · · · · · · · · · · · · · | (continued) |

(continued)

SX System 3.7.8

| ACTIONS (continued) | | | | | | | |
|--|-----------------|--|-----------------|--|--|--|--|
| CONDITION | REQUIRED ACTION | | COMPLETION TIME | | | | |
| BNOTES Only applicable to Unit 1 during replacement of the SX suction isolation valves during Unit 2 Refueling 11 while Unit 2 is in MODE 5, 6, or defueled. | | Enter applicable Conditions and Required Actions of LCO 3.8.1, "AC Sources- Operating," for Emergency Diesel Generator made inoperable by SX. | | | | | |
| One unit-specific SX train inoperable. | | Conditions and Required Actions of LCO 3.4.6, "RCS Loops- MODE 4," for Residual Heat Removal loops made inoperable by SX. store unit-specific | 144 hours | | | | |
| | | train to OPERABLE atus. | | | | | |
| C. Opposite-unit SX train inoperable. | LC | O 3.0.4 is not plicable. | | | | | |
| | SX | store opposite-unit train to OPERABLE atus. | 7 days | | | | |
| D. Required Action and associated Completion | D.1 Be | in MODE 3. | 6 hours | | | | |
| Time of Condition A, B or C not met. | AND | | | | | | |
| | D.2 Be | in MODE 5. | 36 hours | | | | |

SURVEILLANCE REQUIREMENTS

| | | SURVEILLANCE | FREQUENCY |
|------------|---------|--|-----------|
| SR 3.7.8.1 | | Isolation of SX flow to individual components does not render the SX System inoperable. | |
| | | Verify each unit-specific SX manual, power operated, and automatic valve in the flow path servicing safety related equipment, that is not locked, sealed, or otherwise secured in position, is in the correct position. | 31 days |
| SR | 3.7.8.2 | Not required when opposite unit is in MODE 1, 2, 3, or 4. | |
| | | Operate the opposite-unit SX pump for ≥ 15 minutes. | 31 days |
| SR | 3.7.8.3 | Cycle each opposite-unit SX crosstie valve that is not secured in the open position with power removed. | 92 days |
| SR | 3.7.8.4 | Verify each unit-specific SX automatic valve in the flow path that is not locked, sealed, or otherwise secured in position, actuates to the correct position on an actual or simulated actuation signal. | 18 months |
| SR | 3.7.8.5 | Verify each unit-specific SX pump starts automatically on an actual or simulated actuation signal. | 18 months |