



**Argonne**  
NATIONAL  
LABORATORY

*... for a brighter future*



U.S. Department  
of Energy

UChicago

Argonne

## ***Lessons Learned from DOE and Other Site Decommissioning***

*Lawrence E. Boing  
Argonne National Laboratory*

*Advisory Committee on Nuclear Waste –  
Working Group Meeting on Decommissioning Lessons Learned*

*Rockville, MD  
November 14, 2006*

## **Presentation Outline**

- Historical Perspective
- Cost Issue
- Environmental Impact Issue
- Design and Construction Issue
- Other Improvements
- Summary

## **Historical Perspective - 1**

- Some DOE sites/facilities are in closure
- Some DOE sites have limited number of facilities or areas in closure
  - Some will be demolished
  - Some will be reused after decommissioning
- Some facilities are privately owned, but contaminated with Government radioactive materials (contract closure requires restoration)


## **Historical Perspective - 2**

- Many 'one-of-a-kind' facilities designed, operated and with their own unique history and problems
- Many quickly constructed and operated - or at the least not to current day standards – little concern about closure issues
- Recordkeeping issues – 'as built' records, operational history data – some good but lots of poor examples


## **Historical Perspective - 3**

- Many facilities poorly deactivated to a safe shutdown condition in 1950's-1990's; decommissioning inherited these problems
- Generally speaking there are no Decommissioning Funds – slows process of implementing decommissioning
- Poor past communication and past operational limitations on openness complicated stakeholder engagement process and comfort levels
- Labor forces used for decommissioning vary – some 'in-house' forces, others project specific contractors and at closure sites - integrators with subcontractors

# Variety of Facilities




DOE - SRS Fuel Fabrication Facility



DOE Shipping Port Reactor

# Fernald Site - Plant 1



## Plant 1, Sampling Plant



### Interesting Fact:

Workers produced higher enriched uranium-235 liquid that was transferred to Plant 2 to adjust feed concentrations for the production of uranium trioxide ( $UO_3$ ). This liquid was referred to as "sweatener."



### Mission:

Used to receive, sample, store and prepare uranium feed materials for processing.



Demolition Completion:

April 1997



### Demolition Insight:



Several new demolition technologies developed to increase worker safety and efficiency were integrated with existing work plans. Technologies included the oxy-gasoline cutting torch, personal ice cooling vest and the vac-loader insulation vacuum.



**Fluor Fernald**




## Before & After Decommissioning - TFTR



Tokamak Fusion Test Reactor at DOE-PPPL Site, Princeton, NJ



# Facility Re-Use at ANL



CP-5 Vaporsphere



Building 212 Gloveboxes Laboratory

## **Cost Issue - 1**

- Major cost elements are:
  - the labor cost to perform the decommissioning and
  - the cost to manage the generated wastes
  
- Waste disposal at large waste volume generating project sites requires careful planning and cost-benefit analysis for decision making
  
- Management of the interfaces associated with off-site shipments and the associated work involved in establishing and maintaining that process is typically time-consuming
  
- Not to be forgotten is site characterization and the historic site assessment


## Cost Issue - 2

- Clearance (for free release) of larger volumes of material that would not require management as wastes would reduce the costs
- Intact large component/equipment removals save funds as well as schedule and reduce risks
- Find ways to optimize the decommissioning process through 'optioneering' studies including cost-benefit analyses and value engineering
- Industrial safety issues need close monitoring – electrical safety, rigging and lifting, control of contractors - to mention just a few – its very expensive to 'sit and wait' due to work stoppages or other problems

## Cost Issue - 3

- Technologies are available off the shelf to support decommissioning
- Final site end-state must be developed and agreed to early to avoid costly delays and re-work of areas

# ANL JANUS Reactor D&D - Costs Detail



■ Project Management

■ D&D

■ Project Engineering

■ Equipment & Materials

■ Surveillance & Maintenance

■ Waste

■ Characterization

■ Closeout

## **Environmental Issues - 1**

- Highly site specific and site dependent concerns
- NEPA environmental document prepared for each decommissioning project
- Careful consideration to lead times, permitting and regulatory approvals
- Generally speaking has been an evaluate and document issue

## **Waste Management Issues - 1**


- Waste management - the easier and quicker you can move material off the work site the better
- Larger waste material volumes have allowed sites to negotiate for much better rates for some wastes at some commercial disposal sites
- Easier and more cost effective to dispose of material than to decontaminate it – disposal is cheap and clearance is a historic issue
- Many DOE sites have on-site disposal cells which alleviate many waste disposal issues and make the 'flow process' easier – cheaper and whatever bounds the process

## **Waste Management Issues - 2**

- Use of previously unregulated materials - lead based paints, heavy metals, PCB's and asbestos and other chemicals - in a currently regulated materials space
- Management of mixed waste on some projects
- Disposal of very low levels of radioactively contaminated soils with approvals in sanitary landfills or RCRA landfills
- Meet the Waste Acceptance Criteria for the disposal site – don't complicate it any more than necessary



# DOE's Waste Disposal Facility Configuration



# CP-5 Research Reactor D&D



# Demolition Debris



Bagged rubble from building also in the pile

## Packaged Waste



Typical low-level radioactive waste shipment for off-site disposal.

# DOE-Hanford Environmental Restoration Disposal Facility (ERDF)



## Secrets of RFCP Success\*

- Technological and operational innovation
  - Technology experimentation
  - No time to ‘develop’ something – ‘steal’ something !
  - Big technological busts
- No micromanaging
- Proper contract in place to hold accountable yet properly incentivize
- Are we overly compensating/ incentivizing the contractor ?
- Compromise on “Soil Action Levels”

Also see GAO report - GAO 06-352

## **Design & Construction Features - 1**

- Stay away from embedded piping – difficult to assess if contaminated and to remove if needed
- Stay away from large massive concrete structures made by use of a 'one pour' construction technique – disassembly difficult
- Use secondary containment to contain leakages - soil contamination issues from spills, leaks and legacy practices

## Design & Construction Features - 2

- Any NPP or other features which are often touted as an 'O&M' feature can actually also be thought of as a 'decommissioning friendly' feature
  - Reduced impurities in fabrication materials
  - Reduced contamination from plant operations
  - Optimize plant layout for decommissioning – pre-place aids for removal of equipment
  - Waste minimization in facility design/modularization
- Use of standardized 'cookie cutter' designs for future plants allows for optimization of decommissioning implementation



## **Other Possible Improvements**

- Share lessons learned – we are not doing as good of a job as we did in the past in this area
  - IAEA documentation
  - DOE Lessons Learned and Operating Experiences reports
  - NRC Regulatory Information Summaries
  
- Prepare for decommissioning in advance better than we do now – have a ‘living’ decommissioning plan and develop the decommissioning strategy and path forward as the facility is being used – minimal effort and good way to stay current in planning and good public relations
  
- For nuclear industry to remain viable and grow – we must be able to handle legacies of the past - closure of current facilities/sites

## 'Top Ten Lessons Learned'

1. Communications
2. Specialist Support
3. Final Surveys and Endpoints
4. Planning/Cost Estimating
5. Deactivation
6. Waste Management
7. Hazards Assessment
8. Site/Facility History
9. 'OTS' Technologies
10. Facilitate Info Exchange & Teamwork

**Understand what the industry has done and is doing – spend some early planning funds to accomplish this !! Training, Site Visits, Mock ups**

**Expect the unexpected because it will occur sometime or even multiple times during the project !! Contingencies, emergency plans, etc required**

## Lessons Learned Sources

- [www.energy.gov](http://www.energy.gov)
  - DOE Operating Experience weekly reports
  - DOE Lessons Learned website
- [www.iaea.org](http://www.iaea.org)
  - IAEA TECDOC-1394
- [www.nrc.gov](http://www.nrc.gov)
  - NUREG-1757 Volume 2, Appendix O
  - USNRC RIS-02-002 LTP and DP process
  - USNRC RIS-04-008 LTP process
- [www.ornl.gov/ddsc/](http://www.ornl.gov/ddsc/)
  - DDSC Website

## **A Closing Note**

- Remember that decommissioning is not “rocket science” – do not make it any more complicated than necessary
- Learning from experience is difficult – the test comes first and the lessons come later - the exact opposite of how learning typically occurs
- Learn from what others have done and not done – many have walked down this path before you – don’t be afraid to seek out help and ask questions