SECTION I

INSPECTION OBJECTIVES

1. Verify that the testing is conducted in accordance with approved procedures,

2. Independently verify the acceptability of test results, and

3. Evaluate the performance of licensee personnel conducting the test.

SECTION II

INSPECTION REQUIREMENTS

The inspector shall:

1. Schedule an inspection to coincide with this testing.

2. Obtain and review the Auxiliary Building Heating, Cooling and Ventilation System Test Procedure prior to witnessing the test.

3. Review Regulatory Guide 1.68 and applicable portions of the FSAR, SER, Technical Specifications, and docket correspondence. Verify that the Auxiliary Building Heating, Cooling and Ventilation System is adequately tested to ensure that NRC requirements and licensee commitments are satisfied.

4. Observe licensee personnel conducting the test. Verify that:

   a. tests are conducted in accordance with approved procedures,
   b. approved test procedures are available to personnel conducting the test,
   c. test equipment is properly installed,
   d. test data is collected and recorded in the approved manner, and
   e. evaluate the licensee personnel's ability to conduct the test.

SECTION III

INSPECTION GUIDANCE

1. By witnessing this test, the inspector should ensure that important system performance functions are adequately tested. Areas which should be witnessed include (but are not limited to):

   a. integrated system operation and calibration,
   b. system instrumentation, alarms and protective functions,
   c. system ability to maintain proper building pressure differentials,
   d. different control modes of system operation, and
   e. ESFAS functions.

NOTE: Items may be part of other systems tests.