

19/17/83

RELATED CORRESPONDENCE

UNITED STATES OF AMERICA  
NUCLEAR REGULATORY COMMISSION

DOCKETED  
USNRC

'83 OCT 19 AM 1:16

BEFORE THE ATOMIC SAFETY AND LICENSING APPEAL BOARD

OFFICE OF SECRETARY  
DOCKETING & SERVICE  
BRANCH

In the Matter of )

PACIFIC GAS AND ELECTRIC CO. )

(Diablo Canyon Nuclear Power  
Plant, Unit Nos. 1 and 2 )

Docket Nos. 50-275 O.L.  
50-323 O.L.

TESTIMONY OF RICHARD B. HUBBARD

REGARDING DESIGN QUALITY ASSURANCE

I. INTRODUCTION

Q: Please state your name, address, and occupation.

A: My name is Richard B. Hubbard, and my business address is  
1723 Hamilton Avenue, San Jose, California. I am  
vice-president of MHB Technical Associates.

Q: Which of your qualifications and experience are relevant to  
the design quality assurance (QA) matters you address in this  
testimony?

A: I am a Professional Quality Engineer licensed by the State of  
California (license number QU 805). I hold a B.S. in  
Electrical Engineering from the University of Arizona (1960)  
and an M.B.A. from the University of Santa Clara (1969). I  
have nineteen years' experience in the design and manufacture  
of systems and equipment for nuclear power generation  
facilities, including eleven years' experience in responsible  
engineering and manufacturing managerial positions in the

1.

DS03

1 Nuclear Instrumentation Department (1965-1971), Atomic Power  
2 Equipment Department (1971-1975), and Nuclear Energy Control  
3 and Instrumentation Department (1975-1976) of the General  
4 Electric Company (GE). For the past seven years, I, along  
5 with my co-founders of MHB Technical Associates, have  
6 conducted numerous studies pertaining to the safety, quality,  
7 reliability, and economic aspects of nuclear power facilities.

8 From November 1971 to February 1976, I was a Manager of  
9 Quality Assurance for the manufacturing operations at the  
10 San Jose, California, headquarters of GE's Nuclear Energy  
11 Division. I was responsible for the development and  
12 implementation of quality plans, programs, methods, and  
13 equipment to assure that equipment for nuclear plants  
14 designed, manufactured and procured by General Electric met  
15 quality requirements as defined in NRC regulation 10 C.F.R.  
16 Part 50, Appendix B ("Appendix B"); ASME Boiler and Pressure  
17 Vessel Code; customer contracts; and GE corporate policies  
18 and procedures. The product areas include radiation sensors,  
19 reactor vessel internals, fuel handling and servicing tools,  
20 nuclear plant control and protection instrumentation systems,  
21 and control room panels for the Nuclear Steam Supply System  
22 (NSSS) and Balance of Plant (BOP). I was responsible for  
23 approximately 45 exempt personnel, 22 non-exempt personnel,  
24 and 129 hourly personnel with a yearly expense budget of  
25 nearly 4 million dollars and an equipment investment budget  
26 of approximately 1.2 million dollars. While employed by  
27 General Electric, I was responsible for developing a quality

1 system which received NRC certification in 1975. The QA  
2 system was also successfully surveyed for ASME "N" and "NPT"  
3 symbol authorizations in 1972 and 1975, plus ASME "U" and "S"  
4 symbol authorizations in 1975. I was also responsible for  
5 the quality assurance program and its implementation at GE's  
6 spare and renewal parts warehouse in San Jose. I am a member  
7 of the IEEE Nuclear Power Engineering Standards Subcommittee  
8 responsible for the preparation and revision of a number of  
9 Quality Assurance standards for safety-related aspects of  
10 nuclear power facilities.

11 Finally I have testified on safety-related aspects of  
12 nuclear power facilities' quality assurance programs as an  
13 expert witness before the NRC Licensing Boards; before  
14 and at the request of the NRC's Advisory Committee on  
15 Reactor Safeguards; before the Joint Committee on Atomic  
16 Energy of the United States Congress; and before various  
17 other federal and state legislative and administrative  
18 bodies. A summary of my experience and professional  
19 qualifications is set forth in the affidavit of  
20 qualifications that is being filed with this testimony.

21 Q: What sources of information have you relied upon in preparing  
22 this testimony?

23 A: The facts and conclusions set forth in this testimony are  
24 generally based upon the information served on the parties in  
25 the ongoing Diablo Canyon Nuclear Power Station, Units 1 and  
26 2 (Diablo Canyon), licensing proceedings that I have received  
27 and reviewed between September 1981 and September 1983 in my

1 continuing role as technical consultant to counsel for the  
2 Governor of California in these proceedings. I have reviewed  
3 the semi-monthly status reports provided by Pacific Gas and  
4 Electric Company (PG&E) and Teledyne Engineering Services  
5 (TES) concerning the Independent Design Verification Program  
6 (IDVP). Further, I have reviewed the Interim Technical  
7 Reports (ITRs) issued by TES. In addition, I have reviewed  
8 the IDVP Final Report and the Phase I and Phase II reports  
9 released by the Diablo Canyon Project (DCP) resulting from  
10 its Internal Technical Program (ITP). I have prepared and  
11 submitted to the NRC detailed comments concerning  
12 inadequacies in the proposed scope and methodology of the  
13 Phase I and Phase II verification programs. I have discussed  
14 these technical comments at the meetings between Mr. Denton  
15 of the NRC Staff and the intervenors in the Diablo Canyon  
16 proceedings in San Francisco on February 17, 1982, and  
17 September 9, 1982. In addition, I attended and made a  
18 presentation on these matters to the NRC commissioners at a  
19 meeting in Washington, D.C., on November 10, 1982. I  
20 participated in a number of meetings between the various  
21 participants in the Diablo Canyon QA/QC investigations,  
22 including on-site and off-site meetings with personnel from  
23 PG&E, TES, NRC, Bechtel, Stone and Webster Engineering (S&W),  
24 Robert L. Cloud Associates (RLCA), Roger Reedy Incorporated  
25 (Reedy), and Brookhaven National Laboratory (BNL). Finally,  
26 I am familiar with the PG&E license commitments set forth in  
27 the Diablo Canyon Final Safety Analysis Report (FSAR) and the



1 NRC staff reviews as documented in the Safety Evaluation  
2 Report (SER) and its supplements, including Supplements 16  
3 and 18 regarding the staff's most recent reviews of the plant  
4 design.

5 II. PURPOSE

6 Q: What is the purpose of your testimony?

7 A: The purpose of my testimony is to address the level of  
8 assurance provided by the Diablo Canyon design verification  
9 program conducted by the IDVP and ITP. Specifically, this  
10 testimony addresses the matters set forth in Contentions 5,  
11 6, 7, and 8.

12 Q: How is your testimony organized?

13 A: Part III of the testimony provides an overview of design  
14 quality assurance. Terms utilized in the testimony are  
15 defined and key assumptions are identified. My evaluation of  
16 the matters encompassed by Contentions 5, 6, 7, and 8 are set  
17 forth in Parts IV through VII of the testimony respectively.  
18 First, my assessment of the effectiveness of the ITP's design  
19 configuration control efforts to assure that the as-built  
20 Diablo Canyon plant conforms to the design documents is  
21 delineated in Part IV. In Part V, the failure of the  
22 verification program (i.e., the IDVP and the ITP) to reverify  
23 a suitable sample of the design services subcontracted to  
24 Westinghouse by PG&E is presented. The necessity for  
25 identifying all the root causes which led to or provided the  
26 basis for design errors discovered by the IDVP and ITP is  
27 described in Part VI of the testimony, while in Part VII the

1 adequacy of the ITP's quality assurance measures applied to  
2 the design modifications developed since November 1, 1981, is  
3 reviewed. Finally, the conclusions resulting from my review  
4 are summarized in Part VIII.

5 III. OVERVIEW OF QUALITY ASSURANCE/QUALITY CONTROL

6 Q: This testimony is about quality assurance. How is "quality  
7 assurance" defined?

8 A: Appendix B uses the term "quality assurance" (QA) to comprise  
9 "all those planned and systematic actions necessary to  
10 provide adequate confidence that a structure, system, or  
11 component will perform satisfactorily in service."

12 Q: What does "quality control" (QC) mean?

13 A: Appendix B states that "Quality assurance includes quality  
14 control, which comprises those quality assurance actions  
15 related to the physical characteristics of a material,  
16 structure, component or system which provide a means to  
17 control the quality of the materials, structure, component,  
18 or system to predetermined requirements."

19 Q: What is "engineering assurance"?

20 A: Engineering assurance is a term often used to describe the  
21 quality program measures applied by engineering to its design  
22 control activities. For example, the Chief, Engineering  
23 Quality Control, develops and maintains the PG&E Engineering  
24 Department quality control program.<sup>1/</sup>

25 /

---

26  
27 1. Diablo Canyon FSAR, page 17.1-7.

1 Q: Does the preceding mean that not all QA program elements  
2 required by the 18 criteria of Appendix B are necessarily  
3 conducted by personnel of the QA organization?

4 A: Yes. For instance, design verification is normally conducted  
5 by members of the design organization, i.e., the originating  
6 engineer and the reviewing engineer. Other examples of QA  
7 measures often not conducted by the QA organization include  
8 procurement, special process specification and qualification,  
9 document distribution and records maintenance, control of  
10 measuring and test equipment, and handling and storage of  
11 material and equipment. In such cases, the QA organization  
12 normally provides surveillance inspections and audits of the  
13 organization performing the quality activity.

14 Q: What is an "audit"?

15 A: "Audit" is defined in ANSI Standard N45.2.12 as

16 "A documented activity performed in accordance with  
17 written procedures or checklists to verify, by examination  
18 and evaluation of objective evidence, that applicable  
19 elements of the quality assurance program have been  
20 developed, documented and effectively implemented in  
accordance with specified requirements. An audit should not  
be confused with surveillance or inspection for the sole  
purpose of process control or product acceptance."

21 In general there are three major types of nuclear plant  
22 design audits as follows:

23 (a) Program audit - an audit whose purpose is to compare  
24 the design QA program to the applicable regulatory  
25 requirements and Safety Analysis Report (SAR)  
26 commitments.

27

/

1 (b) Process audit - an audit whose purpose is to ascertain  
2 whether the existing design control procedures are  
3 functioning properly and are being effectively  
4 implemented.

5 (c) Product audit - an audit of the design documents whose  
6 purpose is to demonstrate that the design documents such  
7 as specifications and drawings correctly reflect the  
8 applicable regulatory requirements and the design basis  
9 commitments set forth in the SAR.

10 Criterion 18 of Appendix B ("Audits") requires that a  
11 comprehensive system of planned and periodic audits be  
12 carried out to verify compliance with all aspects of the  
13 quality assurance program and to determine the effectiveness  
14 of the program. Thus, audits are intended to identify  
15 conditions adverse to quality so that they can be corrected  
16 and similar repetitive deficiencies precluded in the future.

17 Q: What is an "error"?

18 A: In this testimony the term "error" will be utilized  
19 consistent with the definitions adopted by the IDVP in  
20 Appendix F of the Final Report as follows:

21 Error: A form of program resolution of an Open Item  
22 indicating an incorrect result that was verified as  
23 such. It may have been due to a mathematical mistake,  
24 use of a wrong analytical method, omission of data or  
use of inapplicable data. Each Error was classified as  
the most appropriate of the following:

25 (a) Error Class A: Design criteria or operating limits  
26 of safety related equipment were exceeded and, as a  
result, physical modifications or changes in  
operating procedures were required. . . .

27 /

1 (b) Error Class B: An Error was considered Class B if  
2 design criteria or operating limits of safety  
3 related equipment were exceeded, but were  
4 resolvable by means of more realistic calculations  
5 or retesting. . . .

6 (c) Error Class C: Incorrect engineering or  
7 installation of safety related equipment was found,  
8 but no design criteria or operating limits were  
9 exceeded. No physical modifications were  
10 required. . . .

11 Q: What is an Error Class AB?

12 A: On a number of occasions, the IDVP could not determine  
13 whether resolution would or would not require physical  
14 modifications, so the terminology Error Class A or B (ER/AB)  
15 was used.

16 Q: Did the IDVP also identify a category of discrepancies it  
17 categorized as a "deviation"?

18 A: Yes. The IDVP defined a deviation as follows:

19 Deviation: A departure from standard procedure which is  
20 not a mistake in analysis, design, or construction. No  
21 physical modifications are required. . . .

22 Q: Will you use the term "deviation" in your testimony?

23 A: No. In my judgment the term "deviation" cannot be precisely  
24 differentiated from an "Error C." Consequently, contrary to  
25 the IDVP definition, it appears to me that a departure from a  
26 standard procedure is in fact a mistake and should be  
27 categorized as an Error. Further, my judgment appears to be  
consistent with the QA measures of Criterion 5 of Appendix B,  
which requires in part that activities affecting quality  
shall be prescribed by documented instructions, procedures,  
or drawings and shall be accomplished in accordance with  
these instructions, procedures, or drawings.



1 Q: Does each design error disclosed by the IDVP or NRC audits  
2 represent a multiple failure of the design control system?

3 A: Yes. Each error represents at least two failures; the  
4 original failure or error itself, and the accompanying  
5 failure in the QA program or its implementation which allowed  
6 the original failure to remain undetected. An undetected  
7 error may also represent a failure of more than two "gates"  
8 in the QA program. For example, an error may represent a  
9 failure by the originating design engineer, a failure by the  
10 verifying engineer to detect the error, a failure by the  
11 engineering assurance organization to detect the error in its  
12 surveillance activities, and a failure by the QA organization  
13 to detect the error during its audits. In the preceding, the  
14 term "gate" means a control measure in the design process at  
15 which a design attribute is checked or verified for  
16 conformance. Thus, the effect of the multiple gates is to  
17 provide several opportunities to detect a design  
18 nonconformance.

19 Q: Will a good QA program assure that design failures will be  
20 totally eliminated?

21 A: No. Rather, in designing any complex facility, errors by  
22 the originating engineer are inevitable because people are  
23 not infallible. QA programs recognize human imperfections  
24 and thus impose a management control system to detect  
25 these inevitable errors and, therefore, to ensure that the  
26 facility is, in fact, designed to the requisite licensing  
27 criteria.

1 Q: Will a good QA program detect all design discrepancies?

2 A: No. Clearly while the goal of a QA program for a nuclear  
3 plant is to assure zero defects, it is equally clear that  
4 some defects will escape detection. In my experience, the  
5 gates in the QA program for safety-related items for a  
6 nuclear plant are designed to assure that all critical errors  
7 (Classes A, B, and AB) will be detected. Further, it is  
8 expected that the vast majority of major errors (Class C)  
9 will be detected. A lesser detection rate is acceptable for  
10 minor design discrepancies. Such a systematic concept for  
11 classifying characteristics of error provides a rational  
12 basis for designing the gates in a QA program. Thus, design  
13 features with critical characteristics require special  
14 emphasis in the QA program. Correspondingly, such a system  
15 provides a reasonable basis for applying a lesser degree of  
16 QA controls to design features which might result in a minor  
17 error.

18 Q: Have you made any significant assumptions in preparing  
19 this testimony?

20 A: Yes. Based on my review of the Board's August 16, 1983  
21 order, and my attendance at the pre-hearing conference on  
22 August 23 and 24, it is my understanding that the reopened  
23 Diablo Canyon design quality assurance proceeding will  
24 focus on whether the verification program (the IDVP and  
25 ITP) has demonstrated that the design of Diablo Canyon is  
26 now in compliance with the applicable NRC regulatory  
27 requirements and the PG&E licensing criteria. The

1 licensing criteria (or commitments) are contained in the  
2 PSAR, FSAR, Hosgri Report, SER, SER Supplements, and other  
3 licensing documents including letters from PG&E to the NRC.  
4 Consequently, my testimony will not address the question of  
5 whether PG&E and its design subcontractors complied with the  
6 Commission's design quality assurance regulations and  
7 associated SAR commitments in the period prior to November 1,  
8 1981. Rather, it is now assumed that the design QA process  
9 and its implementation prior to November 1, 1981, cannot be  
10 relied upon to assure the adequacy of design.

11 Q: Does the preceding assumption identify a fundamental question  
12 you will address in the testimony?

13 A: Yes. In my judgment the fundamental question regarding the  
14 Diablo Canyon design, which encompasses all the matters set  
15 forth in the contentions, has as its essence one basic  
16 question: Whether the IDVP and the ITP "after the fact"  
17 verification efforts provide an equivalent level of assurance  
18 regarding the design of Diablo Canyon as would have been  
19 obtained by a QA/QC program conducted in a timely fashion in  
20 compliance with the regulatory requirements of Appendix B.

21 IV. FAILURE TO ASSURE AS-BUILT PLANT CONFORMS TO  
22 TO DESIGN DOCUMENTS

23 Q: What contention addresses the verification program efforts to  
24 assure that the as-built plant conforms to the design  
25 documents?

26 A: Contention 5. This contention, as set forth in the Board's  
27 August 26, 1983 Order, reads as follows:

1 "The verification program has not verified that Diablo  
2 Canyon Units 1 and 2 'as built' conform to the design  
drawings and analyses."

3 Q: What was the initial concern regarding the matters  
4 encompassed by this contention?

5 A: All reviews of PG&E's design control practices for its design  
6 activities conducted prior to November 1, 1981 disclosed  
7 numerous examples where the as-built Diablo Canyon plant  
8 failed to conform to the design documents. This pattern of  
9 configuration control noncompliance was identified by PG&E in  
10 its review in response to NRC Bulletin 79-14. A similar  
11 pattern of differences between the as-built plant and design  
12 documents was disclosed by the IDVP in the Phase I reviews  
13 and by Brookhaven National Laboratory (BNL) in its  
14 independent analysis of the vertical response of the  
15 containment annulus structure.

16 Q: Did other reviewers of the pre-November, 1981 design  
17 activities determine that design and modification problems  
18 indicate the need for improved engineering support?

19 A: Yes. The Institute of Nuclear Power Operations (INPO)  
20 visited the Diablo Canyon site during the week of January 25,  
21 1982. In its report dated February 12, 1982, INPO recommended  
22 changes to the design change control practices as follows:

23 "Improve the existing modification program to ensure  
24 that changes to the plant are controlled and performed  
in a timely manner. For example:

25 a. Complete revisions to affected documentation  
26 before modified systems are returned to service.

27 b. Issue final as-built documentation and update  
procedures as soon as possible.

1 c. Assign review and approval responsibilities for  
2 non-critical modifications to on-site technical support  
3 department engineers." (Governor's Exhibit ("Gov.  
4 Exh.") 11.)

4 Q: Did the DCP initiate changes in its design configuration  
5 control practices for the post-November 1981 design  
6 activities?

7 A: Yes. The engineering review of plant modifications resulting  
8 from IDVP identified errors has been performed in accordance  
9 with Engineering Manual Procedure 3.60N; PG&E Engineering  
10 Manual Procedure No. 3.7, Rev. 5; PG&E Engineering Manual  
11 Procedure No. 3.7, Rev. TR-9; Diablo Canyon Project  
12 Engineer's Instruction No. 13, Rev. 0; and Diablo Canyon  
13 Project Engineer's Instruction No. 13. These procedures  
14 require that Engineering review the result of construction  
15 activities which differ from the Design Change Notice (DCN).

16 Q: Did PG&E initiate other reviews of the as-built condition of  
17 the plant?

18 A: Yes. A description of the design and construction  
19 configuration control process as well as the proposed  
20 as-built walkdown activities by the DCP was provided to  
21 the NRC in a June 24, 1983, letter from Schuyler of PG&E to  
22 Eisenhut.

23 Q: Have the preceding corrective measures fully resolved the  
24 as-built configuration control problem?

25 A: No. The IDVP's recent review of the sample of design  
26 documents resulting from the DCP's corrective action program

27



1 identified a number of instances where the as-built plant  
2 differed from the design documents.

3 Q: Were EOIs issued for these conditions?

4 A: Yes. The most significant EOIs resulting from the IDVP  
5 corrective action review are briefly summarized in Table 8-1  
6 which is appended to the testimony. Configuration control  
7 errors identified by the IDVP included the following:

8 (a) Differences disclosed between "as analyzed" and  
9 "as-built" bolt sizes (EOIs 1120, 1121).

10 (b) Differences disclosed between "as-built" and  
11 "as-analyzed" instrument tubing support (EOI 1123).

12 (c) Design analysis finite element model of the control room  
13 slab used to generate Hosgri spectra not agreeing with  
14 the field verified location of the supporting wall  
15 (EOI 1124).

16 (d) Incorrect valve modeling in DCP seismic reanalyses  
17 (EOI 1133, 1135, 1137).

18 Q: Did the IDVP also identify other discrepancies which were not  
19 the subject to EOI's?

20 A: Yes, the IDVP review of the DCP corrective action measures,  
21 as summarized in the ITRs, identified a large number of  
22 configuration control discrepancies. The discrepancies  
23 disclosed in the ITRs are summarized in Table 5-1 which is  
24 appended to this testimony. For reasons not documented by  
25 the IDVP, the majority of the discrepancies documented in  
26 Table 5-1 were not the subject of EOIs. In my judgment, the  
27 failure of the IDVP to initiate EOIs for these matters is a

1 serious omission. Further, the failure to systematically  
2 initiate EOIs appears to be contrary to the IDVP's procedures  
3 for identifying and evaluating potential errors.<sup>2/</sup>

4 Q: Can you provide examples of configuration control  
5 discrepancies identified by the IDVP which were not  
6 documented in EOIs?

7 A: Yes. Configuration control discrepancies between the  
8 as-built plant conditions and the design documents identified  
9 by the IDVP during its verification of post-November 1981  
10 design activities are denoted with an asterisk in Table 5-1.  
11 Some examples of such configuration control discrepancies in  
12 design documents are the following:

- 13 (a) Pipe weight: A 2000 pound flow element (weight  
14 equivalent to a pipe length of about 2.7 times  
15 pipe diameter) was not included in the DCP model  
(ITR 59).
- 16 (b) Piping geometry: The DCP coded one portion of  
17 20-inch diameter pipe 3 feet shorter and another  
18 portion of 12-inch diameter pipe 4 feet longer,  
19 than indicated by IDVP field verification (ITR 59).
- 20 (c) Support modeling: Support 55S/64R was modeled as a  
21 rigid + Y-directional support, whereas the IDVP  
22 field verification found it to be a gravity support  
23 (ITR 59).
- 24 (d) Valve Modeling: The weights for Valves LCV-113 and  
25 -115 were modeled 45% low for valve bodies and 8%  
26 low for valve operators. In addition, minor  
27 differences in the DCP eccentricity calculations  
were noted (ITR 59).

---

2. The IDVP in its Phase II Program Plan stated that

"Open Item Reports are prepared for the purpose of  
reporting an IDVP response to a QA and Design Control  
Practices deficiency, a violation of the verification  
criteria or an apparent inconsistency identified in the  
performance of the work."

- 1 (e) Support locations: A 3-foot difference in location  
2 of one of the supports was noted (ITR 59).
- 3 (f) Valve Modeling: The DCP analyzed Valve 8805B with  
4 the operator in the vertical position, but an IDVP  
5 field verification found this operator to be in the  
6 horizontal position. Also, differences were found  
7 for valve center of gravity locations for valves  
8 8805A and 8805B and IDVP [sic] and for operator  
9 support locations (ITR 59).
- 10 (g) The IDVP field verification noted a weld across the  
11 top of a member attached to the process pipe.  
12 The DCP drawing did not show this weld (ITR 60).
- 13 (h) The IDVP field verification noted that one of the  
14 four restraints comprising support #98/83 was a  
15 small box frame bilateral rather than a tee-shoe  
16 and clamp assembly as shown on the DCP support  
17 drawing (ITR 60).
- 18 (i) Unintentional restraints, as shown on the DCP  
19 walkdown isometric and by IDVP field verification,  
20 were not explicitly addressed in the analysis  
21 (ITR 61).
- 22 (j) DCP sketches and as-built data did not correlate  
23 with the support analysis. In addition, DCNs for  
24 modifications were omitted from the documentation  
25 package (ITR 63).
- 26 (k) Two of the bolts in the four bolt plate joint  
27 between two column members had been cut out to  
prevent pipe movement interference. The impact of  
the reduced section was not evaluated (ITR 65).

19 Q: Based on the foregoing, what do you conclude?

20 A: The IDVP's reviews to date of a sample of the product (the  
21 design documents) relating from the QA/QC process for the  
22 DCP's corrective action measures demonstrate to me that  
23 configuration control deficiencies continue to exist at  
24 Diablo Canyon. Such configuration differences between the  
25 as-built plant and the design documents are, in my judgment,  
26 contrary to the design control and document control  
27 requirements of Criteria 3 and 6 of Appendix B. The

1 configuration control deficiencies also indicate a failure  
2 to comply with the requirement of Criteria 10 and 11 that  
3 inspections and tests be conducted to verify conformance with  
4 drawings in that the proper conduct of such tests and  
5 inspections would not result in differences between the  
6 as-built plant and design documents remaining undetected.  
7 Finally, the continued existence of discrepancies between the  
8 "as-built" and "as-designed" configuration of the plant  
9 indicate that, contrary to Criterion 16 of Appendix B, the  
10 corrective actions by the DCP have not been adequate to  
11 assure that all conditions adverse to quality are identified  
12 and corrected, and that the cause of the discrepancy is  
13 determined and action taken to preclude repetition of similar  
14 discrepancies.

15 Q: What do you now recommend?

16 A: As a minimum, the verification program should take the  
17 following steps:

18 (a) Examine the numerous past and current examples of  
19 known discrepancies between physical configuration  
20 and design documents, determine the root causes for  
21 those discrepancies, and make all changes in design  
22 documents and physical installations required by  
23 that analysis.

24 (b) Once it is believed that all root causes have been  
25 identified and all resulting discrepancies located  
26 and corrected, the conclusion should be confirmed

1 by examining a random sample of installations and  
2 verifying that they conform to the design  
3 documents.

4 (c) Modify the procedures for the design-construction  
5 configuration control interface to insure that all  
6 deviations from design documents made by  
7 construction are promptly examined, approved and  
8 documented by engineering in compliance with  
9 regulatory requirements.

10 V. FAILURE TO REVERIFY WESTINGHOUSE DESIGN SERVICES

11 Q: What contention addresses the verification program efforts to  
12 reverify the design services subcontracted by PG&E to  
13 Westinghouse?

14 A: Contention 6. This contention, as drafted by the Board in  
15 its August 26, 1983 Order, reads as follows:

16 "The verification program failed to verify that the  
17 design of safety related equipment supplied to PG&E by  
Westinghouse met licensing criteria."

18 Q: To what extent did the ITP reverify the safety-related design  
19 activities performed by Westinghouse for Diablo Canyon?

20 A: The ITP, with assistance from Westinghouse, conducted a  
21 limited verification of the design of Westinghouse supplied  
22 equipment. The ITP review of Westinghouse was characterized  
23 by PG&E as follows:<sup>3/</sup>

24 /

25 /

---

26 3. PG&E's Answer to Governor Deukmejian's Third Set of  
27 Interrogatories, September 19, 1983, page 53.



1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27

INTERROGATORY NO. 51:

With respect to contention 6, do you deny that the verification program failed to verify that the design of safety related equipment supplied to PG&E by Westinghouse met licensing criteria?

RESPONSE TO INTERROGATORY NO. 51:

No. The seismic design of all safety related equipment furnished by Westinghouse was not reanalyzed. Whenever findings of the verification program altered the input to specific pieces of safety-related equipment, that equipment was requalified by Westinghouse and reviewed by the DCP.

Q: Was a similar interrogatory addressed to the IDVP?

A: Yes.

Q: What was its response?

A: The IDVP responded to Governor's interrogatory as follows:<sup>4/</sup>

ANSWER TO INTERROGATORY NO. 51

Since the IDVP did not review any verification that the ITP may have performed of the design of safety-related equipment supplied to PG&E by Westinghouse, the IDVP neither admits nor denies the portion of contention 6 that relates to any such activities by the ITP. With respect to activities by the IDVP, although the IDVP verified the Westinghouse-PG&E interfaces within the scope of the IDVP programs, it did not verify the design of safety-related equipment supplied to PG&E by Westinghouse."

Q: How would you characterize the extent to which the IDVP and the ITP reverified the safety-related design activities performed by Westinghouse for Diablo Canyon?

/

/

---

4. IDVP's Answers to Governor George Deukmejian's Third Set of Interrogatories, September 21, 1983, page 48.

1 A: The preceding statements by PG&E and the IDVP indicate there  
2 is general agreement that neither the IDVP nor the ITP  
3 conducted a systematic verification of the design of  
4 Westinghouse-supplied safety-related Nuclear Steam Supply  
5 Equipment.<sup>5/</sup> In addition, the IDVP did not perform a  
6 verification of the Westinghouse design services summarized  
7 in Appendix A of ITR-9. Rather, the IDVP conducted only a  
8 limited review of the Westinghouse-PG&E design interface.  
9 For example, with respect to seismic design, when the IDVP  
10 examined the transmittal of Hosgri spectra it only verified  
11 on a sampling basis that the applicable spectra were actually  
12 used for equipment qualification. Similarly, the IDVP review  
13 of the non-seismic safety aspects of the Auxiliary Feedwater  
14 System design, as well as the Reedy Phase II QA audit, failed  
15 to involve anything more than an examination of the design  
16 interface between PG&E and Westinghouse.<sup>6/</sup>

17 Q: Did the limited IDVP review disclose potential design errors  
18 in the Westinghouse activities for Diablo Canyon?

19 A: Yes, there is evidence that design errors have remained  
20 undetected by the Westinghouse QA program. For example, the  
21 vertical spectra used by Westinghouse for qualifications of  
22 the accumulators is in error. For the vertical direction,  
23 Westinghouse used two-thirds of the tau filtered spectra,  
24 rather than two-thirds of the unfiltered spectra as committed  
25

---

26 5. Also, see IDVP Final Report, pages 4.1.4-3.

27 6. IDVP Final Report, Section 4.1.3 and ITR-11.

1 to at page 4-3 of the Hosgri Report. Further, in the BNL  
2 review of ITR-11, BNL reviewers noted that errors were  
3 disclosed in 30% of the Westinghouse samples examined by the  
4 IDVP. Therefore, BNL questioned, as I question, the adequacy  
5 of the IDVP's verification of Westinghouse seismic design  
6 activities as follows:<sup>7/</sup>

7 "Further, the large percentage of exceptions (30%),  
8 where Westinghouse qualification spectra did not  
9 completely envelope the Hosgri spectra, would warrant  
additional samples if a complete check of the spectra  
criteria was intended."

10 However, there is no evidence that TES implemented the BNL  
11 suggestion to conduct additional sampling.

12 Q: Was the IDVP review of Westinghouse design activities further  
13 limited?

14 A: Yes. For example, the verification of system design  
15 pressures and temperatures for safety-related systems,  
16 including its use in equipment specifications, resulting from  
17 a generic concern were not included in the IDVP's additional  
18 verification program for items within the Westinghouse design  
19 scope, but rather were limited by the IDVP to PG&E design  
20 scope systems.<sup>8/</sup>

21 Q: Did the ITP's limited review also reveal design errors in the  
22 Westinghouse activities?

23 A: Yes. The seismic review of the main control boards (MCB)  
24 conducted by Westinghouse in response to new spectra for the

---

25 7. Summary and Evaluation Report, ITR-11, TR-5511-2, Rev. 0,  
26 Brookhaven National Laboratory, November 2, 1982. (Gov. Exh. 12.)

27 8. SER Supplement 18, page C.4-25.

1 auxiliary building developed by the ITP identified an error  
2 in the original seismic qualification analysis. The MCB was  
3 procured by Westinghouse from Reliance, and Reliance used a  
4 private consultant to seismically qualify the MCB by  
5 analysis. The original analysis in the early 1970's  
6 predicted the lowest natural frequency of the MCB to be above  
7 70 Hz based on the analytical model used. In the current  
8 evaluation process, the MCB was modeled using field  
9 measurements and results of in-situ tests. The in-situ tests  
10 pointed out the existence of natural frequencies between 15  
11 to 28 Hz which is much below the 71 Hz calculated originally.  
12 Because of this error, and because of the severity of the  
13 current Hosgri spectra at the base of the MCB in the 15 to 33  
14 Hz range, Westinghouse has provided modifications to the MCB.<sup>9/</sup>

15 Q: Based on the foregoing, what do you now conclude?

16 A: It is evident that the conclusions resulting from the IDVP  
17 and ITP reviews on samples of other design service  
18 contractors cannot be extended to provide meaningful  
19 conclusions as to the adequacy of Westinghouse-supplied NSSS  
20 equipment or of the adequacy of Westinghouse design services.  
21 Further, Westinghouse was the responsible design organization  
22 for over 70% of the Diablo Canyon safety-related systems. As  
23 NSSS contractor, Westinghouse had responsibility to develop  
24 and implement the majority of the non-structural Diablo  
25

---

26 9. SER Supplement 18, Section 3.5.3. Also, see transcript  
27 of Westinghouse/PG&E/NRC meeting on May 20, 1983, regarding  
seismic qualification of the MCB.

1 Canyon safety features committed to by PG&E in the FSAR and  
2 other licensing commitments provided in response to the NRC  
3 regulations. In particular, Westinghouse supplied the Diablo  
4 Canyon designs provided to assure compliance with a  
5 significant number of the General Design Criteria set forth  
6 in Appendix A to 10 C.F.R. Part 50 of the NRC regulations.

7 Q. What do you recommend?

8 A. What is needed is a systematic verification of Westinghouse  
9 design activities. The verification should include a  
10 suitable sample of Westinghouse design documents and  
11 activities sufficient to assure that all Diablo Canyon  
12 licensing criteria are met, to assure the efficacy of the  
13 Westinghouse QA process, and to assure that all basic causes  
14 and generic implications of any errors detected have been  
15 thoroughly assessed.

16 VI. FAILURE TO IDENTIFY ROOT CAUSES

17 Q: What contention addresses the verification program efforts to  
18 identify the root causes of the design errors detected by the  
19 verification program?

20 A: Contention 7. This contention, as set forth by the Board's  
21 Order, reads as follows:

22 "The verification program failed to identify the root  
23 causes for the failures in the PG&E design quality  
24 assurance program and failed to determine if such  
failures raise generic concerns."

25 Q: How do you define "root cause"?

26 A: "Root cause" is defined as the underlying basis that precedes  
27 and usually induces an effect or result.



1 Q: Does the term "root cause" mean the same as "basic cause" as  
2 used by the IDVP?

3 A: Yes. The IDVP in Section 6.3 of its Final Report defined  
4 basic cause as "the underlying problem or concern which led  
5 to or provided the basis for an identifiable error of  
6 commission or omission," which is equivalent to the preceding  
7 definition of root cause.

8 Q: What does the term "generic concern" mean?

9 A: "Generic concern" refers to the potential of each error to  
10 exist in a similar manner in other, unreviewed parts of the  
11 plant. Thus, the corrective action verification for a  
12 potential generic concern should be conducted to the depth  
13 and extent required to ascertain whether the specific error  
14 is one of a number of similar errors in other, unreviewed  
15 items of the Diablo Canyon plant.

16 Q: Were generic concerns identified by the IDVP?

17 A: Yes. Generic concerns were purportedly identified by the  
18 IDVP "where one or more specific errors had been identified  
19 or because the IDVP believed that a generic concern could  
20 exist even though a specific concern was satisfactorily  
21 resolved."<sup>10/</sup> Thus, the term generic concern, when used by  
22 IDVP, is intended to indicate that the error (Class A or B)  
23 is "potentially applicable to structures, systems, or

24 /

25 /

---

26  
27 10. IDVP Final Report, Section 3.5.5, page 3.5-4.

1 components in addition to that for which it was first  
2 identified.<sup>11/</sup>

3 Q: Was an assessment of the basic cause of the identified errors  
4 required of the IDVP?

5 A: Yes. The Commission Order and the November 19, 1981 Staff  
6 Letter both require that the IDVP conduct an assessment of  
7 the basic cause of all the design errors identified by the  
8 IDVP. The Staff and the Commission required that the IDVP  
9 provide the following three part assessment for each  
10 identified design error:

11 "A technical report that fully assesses the basic cause  
12 of all design errors identified by this program, the  
13 significance of design errors found, and their impact on  
14 plant design." See Commission Order, Attachment 1, at  
part 1(a)(5)(b) and Staff Letter at parts 1(b), 2(b),  
and 3(b).

15 Q: Where is the IDVP assessment documented?

16 A: The IDVP Final Report in Section 6.0 contains its evaluation  
17 with the basic cause of design errors documented in a very  
18 general manner in Section 6.3. The significance is set forth  
19 in Section 6.4, while the impact is briefly discussed in  
20 Section 6.5.

21 Q: Did the ITP also provide a general statement describing its  
22 determination of the basic causes of the identified errors?

23 A: Yes. The ITP documentation of basic causes is provided in  
24 Section 1.8 of the Phase I Final Report and Section 3.0 of  
25 the Phase II Final Report. In no case, however, did the ITP,  
26

---

27 11. IDVP Final Report, Section 5.1, page 5.1-2.

1 or the IDVP, correlate the basic causes cited to the  
2 identified errors.

3 Q: Should the IDVP and ITP have made such a correlation?

4 A: Yes. The IDVP's and the ITP's failure to make this correla-  
5 tion is contrary to the corrective action requirements of  
6 Criterion 16 of Appendix B.<sup>12/</sup>

7 Q: Why is this so?

8 A: Criterion 16 requires that a QA audit ascertain the causes of  
9 QA program failings so that an appropriate corrective action  
10 program can be devised. Part of any proper corrective action  
11 program is a determination as to whether the observed failure  
12 has generic implications. Fundamental to any investigation  
13 of the generic implication of any QA failure is a  
14 determination of the root cause of that failure. It is only  
15 when the root cause of a failure is identified that the  
16 question of its generic implications can be addressed.  
17 Instead of analyzing the root cause of each design error it  
18 uncovered as a mechanism toward assessing the generic  
19 implications of that error, the IDVP and the ITP provided no  
20 more than global conclusions regarding basic cause with no  
21 specific reference to any of the identified errors. Further,  
22 the global basic causes identified by the IDVP and the ITP  
23 primarily relate to the seismic errors. Thus, the multiple  
24 failures (basic causes) which resulted in the non-seismic

---

25 12. The failure to develop the correlation is also contrary  
26 to the requirements for the assessment of basic causes set forth  
27 in the Commission Order and the Staff's November 19, 1981,  
Letter.

1 design errors were not systematically addressed. This is a  
2 serious omission.

3 Q: What do you mean by multiple basic causes?

4 A: In general each error identified by the IDVP was the result  
5 of multiple causes. For example, as discussed in Part III of  
6 this testimony, each design error detected by the IDVP or ITP  
7 represents at least two failures: the failure itself,  
8 and the accompanying failure or failures in the QA gating  
9 program or its implementation which allowed the original  
10 failure to remain undetected. Thus, an adequate evaluation  
11 of the basic cause must address the cause underlying each  
12 failure.

13 Q. Did the ITP or IDVP assess the potential generic concern  
14 which can result due to the failure to establish or implement  
15 the QA/QC measures required by Appendix B?

16 A. No. This is a serious deficiency in the verification  
17 program's assessment of basic causes.

18 Q: Is it possible to go back in time to ascertain the cause of a  
19 design error?

20 A: Yes. Indeed, Criterion 16 of Appendix B requires that the  
21 causes of conditions adverse to quality be identified and  
22 corrected.

23 Q: Can you provide an example of how to conduct the two part  
24 assessment of basic causes for a particular error?

25 A: Yes. The original mirror image design error provides such an  
26 example. The error was that the diagram used to locate  
27 Vertical Seismic Floor Response (VSFR) for the Unit 1

1 containment annulus was applicable to Unit 2 but was  
2 identified as being that of Unit 1. Since the units are  
3 opposite hand, this resulted in an incorrect orientation of  
4 VSFR spectra for Unit 1 component and system design. The  
5 origin of the error was in the PG&E submittal to its  
6 principal seismic design subcontractor, John A. Blume and  
7 Associates (Blume), of an unverified, unlabeled, handwritten  
8 sketch of the Unit 2 opposite hand geometry in place of the  
9 Unit 1 geometry.<sup>13/</sup> Blume personnel further compounded the  
10 "sketch" error by one of their own. Blume assumed that the  
11 layout of the annulus areas of Units 1 and 2 were identical  
12 when, in fact, they were mirror images.<sup>14/</sup> In my judgment  
13 the underlying cause of the initial failure was the breakdown  
14 of design interface control in that unverified and  
15 uncontrolled design data were provided to Blume contrary to  
16 Criteria 3, 4, and 5 of Appendix B regarding design control,  
17 procurement document control, and procedural control.

18 The initial failure was not detected because the design  
19 control and document control measure failed to assure, as  
20 required by Criteria 3 and 6, that documents were reviewed  
21 for adequacy and approved for release by authorized personnel  
22 and were distributed to and used at the location where the  
23 prescribed activity was performed. In addition, Blume was  
24 not contractually obligated by PG&E to a QA program until

---

25 13. LER 81-002/01T-0, October 12, 1981. (Gov. Exh. 13.)

26 14. NRC Inspection Report 50-275/81-29, page 2. (Gov.  
27 Exh. 14.)



1 1978, eight years after Appendix B was adopted and twelve  
2 years after Blume's first engineering services on Diablo  
3 Canyon, contrary to the requirements of Criterion 2 that a QA  
4 program be established "at the earliest practicable time."  
5 Also, PG&E's qualification and evaluation of service  
6 contractors as required by Criterion 7 did not occur until  
7 after completion of the subject engineering. Finally, audits  
8 of suppliers, such as Blume, were not carried out in a timely  
9 fashion to verify compliance with the QA program requirements  
10 and to determine the effectiveness of the program as required  
11 by Criterion 18. Thus, the appropriate corrective action  
12 measures as set forth in Criterion 16 were not initiated by  
13 PG&E or its subcontractor.

14 Q: Did the IDVP or ITP conduct such a two part evaluation as you  
15 have suggested?

16 A: No. In no design error did the IDVP or ITP specifically  
17 identify and document the second failure or failures in  
18 the quality assurance program or its implementation  
19 which allowed the initial failure to remain undetected.  
20 Further, in most cases, neither the IDVP nor the ITP  
21 provided documentation identifying the underlying cause,  
22 or series of causes, leading to the initial failure.

23 Q: Do you have any examples to illustrate the weaknesses you  
24 described in the IDVP and ITP treatment of basic cause?

25 A: Yes. The resolutions of EOI's No. 7002, 8010, 8017, 8022,  
26 8023, and 8060 all demonstrate a failure to completely  
27 address the basic causes of the identified errors.

1 Q: How does the resolution of EOI 7002 exemplify a failure to  
2 address the basic cause?

3 A: EOI 7002 resulted from an R. F. Reedy finding that no  
4 objective evidence was available to demonstrate that the  
5 effects of jet impingement on components inside containment  
6 had been considered.<sup>15/</sup> In order to resolve EOI 7002, the  
7 DCP developed the analysis of jet impingement inside  
8 containment as committed to in FSAR Section 3.6, paragraph  
9 3.6.<sup>16/</sup>

10 The above resolution, while it may address the specific  
11 error which led to the establishment of EOI File No. 7002,  
12 does not address the question of why no documentation of the  
13 jet impingement review was available when the FSAR stated  
14 that a review had been performed.

15 PG&E, in its Final Report on Phase II of the ITP,  
16 discussed the cause of EOI 7002 as follows:<sup>17/</sup>

17 As was typical for plants of this vintage, formalized  
18 analyses for jet impingement were not done for the  
19 original plant design, which was based on inherent  
20 separation of safety systems through an appropriate  
21 arrangement of equipment, piping, walls, and other  
22 structures. The current NRC guidelines for formal jet  
impingement evaluation defined in Section 3.6 of the  
Standard Review Plans had not been issued at that time.  
Jet impingement effects were, however, taken into  
account. The plant arrangement was designed so that a

---

23 15. Potential Program Resolution Report, File No. 7002,  
24 revision 0, IDVP, October 11, 1982. (Gov. Exh. 15.)

25 16. Open Item Report, File No. 7002, revision 5, IDVP, July  
26 26, 1983. (Gov. Exh. 16.)

27 17. "Phase II Final Report, Design Verification Program",  
Pacific Gas & Electric Company, June 1983, pages 3-17.

1 catastrophic break of a high-energy line or other  
2 unexpected phenomenon would not affect a redundant  
3 safety system, and the original design included  
4 appropriate consideration of break locations and  
5 calculations for jet impingement forces on major  
6 structures.

7 As nuclear plant design progressed and requirements  
8 became more formalized and were upgraded, more rigorous  
9 documentation of the adequacy of jet impingement design  
10 was required by the NRC. The DCP has upgraded the  
11 original design basis by the performance of a  
12 formalized, rigorous investigation of jet impingement  
13 utilizing the current requirements and techniques."

14 One can readily understand that when Diablo Canyon was  
15 first designed, there was no requirement for a formal and  
16 rigorous jet impingement analysis. However, between the  
17 original design of Diablo Canyon and October 11, 1982 (when  
18 the R. F. Reedy finding was dated), PG&E made a commitment in  
19 their FSAR that the effects of jet impingement inside  
20 containment would be addressed. Therefore, the PG&E  
21 explanation does not identify the the reason why PG&E's QA  
22 program did not identify this failure to perform the jet  
23 impingement analysis earlier?

24 Q: How does the resolution of EOI 8010 exemplify a failure to  
25 address the basic cause?

26 A: EOI 8010 resulted from an IDVP concern that low pressure  
27 piping and components would be overpressurized by a variety  
28 of operational occurrences.<sup>18/</sup> In order to resolve EOI 8010,

29 /

30 /

---

31 18. Open Item Report, File No. 8010, revision 0, IDVP,  
32 September 13, 1982. (Gov. Exh. 17.)

1 PG&E implemented modifications to assure the protection of  
2 low pressure components.<sup>19/</sup> Further, to resolve the generic  
3 implications raised by EOI's 8009, 8010 and 8062, the DCP  
4 provided additional verification of the selection of design  
5 temperature, pressure, and differential pressure across power  
6 operated valves.

7 The IDVP reviewed part of the DCP reanalysis and  
8 reported its findings in ITR 46. On page 2-2 of ITR 46, the  
9 IDVP stated, "concerns similar to those originally found in  
10 the pressure/temperature review of the AFW system were found  
11 by PG&E also to exist in the Main Steam System and portions  
12 of the Component Cooling Water System." However, the IDVP  
13 documentation of the resolution of EOI 8010 and of the  
14 additional verification of design temperature/pressure does  
15 not identify the reason behind the original error, or the  
16 subsequently-identified errors in other systems.

17 PG&E, in its Final Report on Phase II of the ITP,  
18 discussed the cause of EOI 8010 as follows:<sup>20/</sup>

19 "...EOI 8010 arose as a result of a later system  
20 modification to improve start-up flow to the coolers.  
21 In implementing the flow improvement, the designers  
22 failed to recognize the small increase in pressure  
23 resulting from the design change."

24 While the above explanation does identify a reason why  
25 the error (EOI 8010) occurred, it raises further questions  
26

---

25 19. Error Report, File No. 8010, revision 8, IDVP, March 4,  
26 1983 (Gov. Exh. 18); Program Resolution Report, File No. 8010,  
27 revision 11, IDVP, June 1, 1983 (Gov. Exh. 19).

20. Ibid. 17, pages 3-12.

1 which should be answered before the basic cause may be  
2 considered to have been addressed. For instance, does a  
3 procedure exist which requires the designer to evaluate  
4 possible pressure changes whenever a modification is made to  
5 a fluid system? Also, what caused the additional errors  
6 which were reported in ITR 46 but given no EOI designation?

7 For the above reasons, the resolution of EOI 8010 does  
8 not address the basic cause leading to the specific error,  
9 nor does it identify the QA error which allowed the original  
10 error to remain undetected.

11 Q: How does the resolution of EOI 8017 exemplify a failure to  
12 address the basic cause?

13 A: EOI 8017 resulted from an IDVP concern that separation  
14 criteria were violated by an electrical control transfer  
15 switch where control power from two redundant safety-related  
16 sources was brought together.<sup>21/</sup> In order to resolve the  
17 specific concern of EOI 8017, the DCP modified the transfer  
18 switch to provide separation of the power sources.<sup>22/</sup>  
19 Further, in order to resolve the generic implications of  
20 EOIs 8017 and 8057, the DCP provided additional verification  
21 of electrical separation which the IDVP reviewed and reported  
22 in ITR 49. On page 2-1 of ITR 49, the IDVP states, "The PG&E  
23 review resulted in the identification of separation and  
24 /

---

25 21. Open Item Report, File No. 8017, revision 0, IDVP,  
26 October 4, 1982. (Gov. Exh. 20.)

27 22. Ibid. 17, pages 3-19.



1 single failure concerns similar to those addressed in the  
2 initial sample."

3 The IDVP documentation did not address the reason for  
4 the original error, or the QA error which allowed the  
5 original error to remain undetected. PG&E, in their Final  
6 Report on Phase II of the ITP, discussed the cause of EOI  
7 8017 as follows:<sup>23/</sup>

8 "In the early design of the plant, it was not intended  
9 that the separation criteria be literally applied all  
10 the way to the redundant devices and terminal blocks  
11 where the circuits came together within panels. Within  
12 that context, it was a standard practice to weigh  
13 competing considerations for low probability failure  
14 events. The value of operational flexibility gained by  
15 cross-tying redundant trains, for example, would be  
16 weighed against the unlikely occurrence of failure at  
17 the point of the cross-tie. Often the gain in  
18 operational flexibility outweighs the risk of the local  
19 failure at the point of cross-tie."

20 As in the case of EOI 7002, it is readily understood  
21 that certain requirements were not effective at the time of  
22 time of Diablo Canyon's initial design. However, the error  
23 which led to the establishment of EOI file 8017, and the  
24 errors which were identified in the DCP's additional review  
25 of separation represent violations of separation criteria  
26 which were committed to in the FSAR. PG&E's explanation does  
27 not address the question of how these errors occurred or how  
they remained undetected by the PG&E QA program.

Q: How does the resolution of EOI 8022 exemplify a failure to  
address the basic cause?

---

23. Ibid. 17, pages 3-20 and 3-21.

1 A. EOI 8022 resulted from an IDVP concern that certain circuit  
2 breakers in the 4160V safety-related electrical distribution  
3 system had interrupting ratings less than the short circuit  
4 interrupting currents in certain operating conditions.<sup>24/</sup> In  
5 order to resolve EOI 8022, the DCP obtained a letter from GE  
6 documenting the actual short circuit interrupting capacities  
7 of the circuit breakers as significantly higher than the  
8 rated capacity, and also higher than the calculated  
9 duties.<sup>25/</sup>

10 Although the GE letter may have resolved the specific  
11 concern of the under-capacity of circuit breakers, neither  
12 the IDVP nor the DCP documentation has addressed the question  
13 of how the design error originally came about, and why the  
14 error was not detected by the PG&E QA program.

15 Q: How does the resolution of EOI 8023 exemplify a failure to  
16 address the basic cause?

17 A: EOI 8023 resulted from an IDVP concern that, under certain  
18 accident conditions, the voltages on the Engineering  
19 Safeguards 480V system buses may be insufficient for  
20 continuous operation.<sup>26/</sup> In order to resolve EOI 8023, PG&E

21 /

---

23 24. Open Item Report, File No. 8022, revision 0, IDVP,  
24 October 12, 1982. (Gov. Exh. 21.)

25 25. Error Report, File No. 8022, revision 5, IDVP, March 10,  
26 1983; Interim Technical Report 24, revision 1, IDVP, May 4, 1983.  
27 (Gov. Exh. 22.)

26 26. Open Item Report, File No. 8023, revision 0, IDVP,  
27 October 12, 1982. (Gov. Exh. 23.)

1 adjusted the transformer tap settings on the 230 kV start-up  
2 transformers and on Buses 1F, 1G, and 1H.<sup>27/</sup>

3 The IDVP documentation does not address the question of  
4 why the potential for undervoltage existed in the design, nor  
5 why the condition was not detected by PG&E's QA program. The  
6 basic cause of EOI 8023 is not discussed in PG&E's Final  
7 Report on Phase II of the ITP. Thus, neither the IDVP nor  
8 PG&E have addressed the basic cause of EOI 8023.

9 Q: How does the resolution of EOI 8060 exemplify a failure to  
10 address the basic cause?

11 A: EOI 8060 resulted from an IDVP concern that an interaction  
12 involving the runout control system could limit Auxiliary  
13 Feedwater (AFW) flow to less than minimum values in certain  
14 operating conditions.<sup>28/</sup> In order to resolve EOI 8060, PG&E  
15 calculated new runout control system setpoints and  
16 implemented the changes in the field.<sup>29/</sup>

17 The IDVP documentation does not address the question of  
18 why the design included the potential for adverse interaction  
19 between the runout control system and AFW flow, nor does it  
20 identify the QA error which allowed the design error to  
21 remain undetected. The basic cause of EOI 8060 is not

22 /

---

23 27. Program Resolution Report, File No. 8023, revision 5,  
24 IDVP, March 11, 1983. (Gov. Exh. 24.)

25 28. Open Item Report, File No. 8060, revision 0, IDVP,  
26 October 29, 1982. (Gov. Exh. 25.)

27 29. Error Report, File No. 8060, revision 5, IDVP, March 15,  
1983. (Gov. Exh. 26.)

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27

discussed in PG&E's Final Report on Phase II of the ITP.  
Therefore, neither the IDVP nor PG&E has addressed the basic  
cause of EOI 8060.

Q: Are the preceding six EOI resolutions the only examples of  
failures by the IDVP and ITP to address the basic causes of  
design errors?

A: No, they are only indicative of the methodology used by the  
verification program to identify basic causes for errors.  
Further examples have not been presented in my testimony in  
the interest of brevity.

Q: In summary, what is your conclusion regarding Contention 7?

A: The corrective action measures initiated by the ITP in  
response to the design errors identified by the IDVP do not  
in a number of cases fully respond to the root cause.  
Therefore, potential generic concerns were not raised, or  
were only partially addressed by the verification program.

/

/

/

/

/

/

/

/

/

/

/

/

1 VII. INADEQUACIES IN THE ITP QA MEASURES

2 INCLUDING ITS CORRECTIVE ACTION PROGRAM

3 Q: What contention addresses the adequacy of the ITP's quality  
4 assurance measures applied to the design modifications  
5 developed since November 1, 1981 as well as the sufficiency  
6 of the ITP's Corrective Action Program?

7 A: Contention 8. This contention, as set forth by the Board,  
8 reads as follows:

9 The ITP failed to develop and implement in a timely  
10 manner a design quality assurance program in accordance  
11 with 10 CFR Part 50, Appendix B to assure the quality of  
12 the recent design modifications to the Diablo Canyon  
13 facility and the IDVP failed to ensure that the  
corrective and preventative action programs implemented  
by the ITP are sufficient to assure that the Diablo  
Canyon facilities will meet licensing criteria.

14 Q: What sources of information measure the adequacy of the ITP's  
15 quality assurance program including the Corrective Action  
16 Program activities?

17 A: There are three measures of the post-November 1, 1981 QA  
18 program and its implementation: design product verifications,  
19 design process audits; and regulatory compliance reviews.

20 Q: What do you mean by design product verification?

21 A: A design product verification provides a comparison of the  
22 Diablo Canyon design documents with the applicable design  
23 criteria. Such a review constituted the major focus of the  
24 IDVP's verification efforts. The IDVP corrective action  
25 review addressed a sample of the seismic and non-seismic  
26 safety-related design activities conducted since November 1,  
27 1981. The design product verification is also very important



1 since it provides a direct measure of the adequacy of the  
2 as-released for construction design documents.

3 Q: What were the results of the IDVP review?

4 A: The errors identified in the IDVP's design product review of  
5 design modifications since November 1, 1981 are summarized in  
6 Table 8-1 which is appended to this testimony. As set forth  
7 in Table 8-1, the review to date has identified approximately  
8 five (5) errors of Classes A and B, twelve (12) Class C  
9 errors, and one (1) so-called deviation.

10 Q: Did the IDVP in its review of the ITP Corrective Action  
11 Program also identify other discrepancies which were not the  
12 subject of EOIs?

13 A: A design product verification provides a comparison of the  
14 Diablo Canyon design documents with the applicable design  
15 criteria. Such a review constituted the major focus of the  
16 IDVP's verification efforts. The IDVP corrective action  
17 review addressed a sample of the seismic and non-seismic  
18 safety-related design activities conducted since November 1,  
19 1981. The design product verification is also very important  
20 since it provides a direct measure of the adequacy of the  
21 as-released for construction design documents.

22 Q: What were the results of the IDVP review?

23 A: The errors identified in the IDVP's design product review of  
24 design modifications since November 1, 1981 are summarized in  
25 Table 8-1 which is appended to this testimony. As set forth  
26 in Table 8-1, the review to date has identified approximately

1        five (5) errors of Classes A and B, twelve (12) Class C  
2        errors, and one (1) so-called deviation.

3        Q: Did the IDVP in its review of the ITP Corrective Action  
4        Program also identify other discrepancies which were not the  
5        subject of EOIs?

6        A: Yes, as previously discussed in Part IV of this testimony,  
7        the IDVP's corrective action review identified numerous  
8        design discrepancies which could have, but did not result in  
9        the issuance of an EOI. A list of such discrepancies is  
10       provided in Table 5-1 which is appended to this testimony.

11       Q: Should the IDVP have issued EOIs for the discrepancies  
12       tabulated in Table 5-1?

13       A: Yes. In my judgment, the discrepancies in general met at  
14       least one of the IDVP's criteria for issuing an EOI in that  
15       they represented:

16                    (a) A deficiency in a QA and Design Control  
17                    Practice;

18                    (b) A violation of the verification criteria; or

19                    (c) An apparent inconsistency identified in the  
20                    performance of the work.

21       Q: What is the significance of the IDVP's failure to issue EOIs  
22       for identified discrepancies?

23       A: The EOIs identified by the IDVP in its review of the DCP  
24       Corrective Action Program understated the nature and extent of  
25       the discrepancies actually discovered by the IDVP.

26       A: Can you provide an example of how this understatement is  
27       reflected in the IDVP's Final Report?

1 A: In its Final Report, the IDVP concluded that "only one addi-  
2 tional analysis was found to use an improper value (stress  
3 intensification factor), as reported in EOI 1138"<sup>30/</sup>  
4 Contrary to the IDVP's conclusion, Table 5-1 of this testimony  
5 sets forth over 10 examples drawn from ITR 59 where improper  
6 values of stress intensification factors (SIFs) were disclosed  
7 in the IDVP's verification of the ITP's post-November 1981  
8 design activities. Moreover, further examples of misapplied  
9 SIFs, as document in ITR 60, are also presented in Table 5-1.

10 Q: What do you mean by design process audits?

11 A: A design process audit provides information concerning whether  
12 the DCP effectively implemented its quality assurance program.

13 Q: What are the key documents which constitute the DCP design  
14 quality assurance program?

15 A: The following documents form the DCP design quality assurance  
16 program and implementing procedures:

17 (a) The Bechtel Topical Report BQ-TOP-1, Rev. 3A, October  
18 1980 (Gov. Exh. 27), describes the quality assurance  
19 program to be implemented by the DCP. Additional  
20 information and clarification of the program was  
21 provided to the NRC in a letter dated August 13, 1982,  
22 which modified the scope of the DCP QA Program;

23 (b) The Bechtel Nuclear Quality Assurance Manual (NQAM)  
24 (Gov. Exh. 28), as amended to correctly identify the  
25 Diablo Canyon Project quality assurance policies;

---

26  
27 30. IDVP Final Report, Section 5.6, page 5.6-2.

1 (c) The Bechtel Quality Assurance Department Procedures  
2 Manual (QADP) (Gov. Exh. 29) as amended for DCP provides  
3 procedures for Quality Assurance Department personnel  
4 utilized on the project;

5 (d) The PG&E Engineering Department Engineering Manual  
6 (Gov. Exh. 30) establishes the controls and procedures  
7 to be used by the DCP for design activities;

8 (e) The Diablo Canyon Project Engineering Instructions (PEI)  
9 (Gov. Exh. 31) provide supplemental instruction for the  
10 application of the Engineering Manual to the Diablo  
11 Canyon Project.

12 Q: Was a design process audit of the DCP quality assurance  
13 program conducted by the IDVP?

14 A: Yes, the results of a series of design control audits  
15 conducted by Reedy between November 11, 1982 and December 7,  
16 1982 are set forth in ITR 41. In addition, Reedy performed a  
17 follow-up audit on March 17, 1983.

18 Q: What were the results of Reedy's design process audit?

19 A: The IDVP audit basically took a snapshot of the DCP design QA  
20 program at one point in time. In its limited review, the  
21 IDVP design control audit disclosed 24 deficiencies in the  
22 DCP quality assurance program development and implementation  
23 including incomplete records documentation, lack of  
24 procedures, procedures not being followed, inadequate  
25 training, failure to implement commitments in a timely  
26 manner, inadequate document control, deviations in design  
27 control activities, and failure to control procurement

1 activities. However, these conditions were determined by the  
2 IDVP "to be due to incomplete documentation, because this  
3 audit was performed in the early stages of the DCP QA Program  
4 implementation."<sup>31/</sup> While it is true that the DCP QA program  
5 was only established on August 20, 1982, it should also be  
6 remembered that the Reedy audit took place nearly one year  
7 after the issuance of the Order suspending the Diablo Canyon  
8 license. Thus, in my judgment one would have expected more  
9 progress in QA program implementation.

10 Q: Do you agree that none of the audit results identified by  
11 Reedy could have either a potential or real impact on the  
12 quality of design activities?

13 A: No. The Diablo Canyon QA/QC measures presumably were drawn  
14 up such that (a) the QA/QC measures were designed to achieve  
15 a necessary objective; and (b) if implemented properly, the  
16 QA/QC measures would have achieved the objective. In fact,  
17 however, the necessary implementation was not achieved.  
18 Instead, over a number of years, there were recurring  
19 observations of lack of necessary QA/QC attention.

20 The failure to implement the design control measures  
21 represents a serious concern primarily because it reflects a  
22 lack of discipline in and management attention to the QA/QC  
23 program. The QA/QC management program requires specified  
24 standards be reliably and repeatedly achieved, and that  
25 program objective was not obtained. In QA/QC, such lack of  
26

---

27 31. ITR 41, page 2.



1 attention to prescribed measures cannot be tolerated. Each  
2 QA/QC measure, once issued by responsible management, must be  
3 assumed to be important. The fact that the IDVP now in  
4 hindsight apparently finds the instances of non-compliance to  
5 be acceptable (or at least not a significant concern)  
6 represents a lack of attention to the necessary discipline  
7 and detail which constitutes a basic ingredient of a  
8 successful QA/QC program. Further, Mr. Reedy acknowledged  
9 during his deposition that he had not reviewed the recent  
10 EOI's 1120 to 1144 resulting from the IDVP's review of  
11 corrective action in order to determine the significance of  
12 the errors in terms of the QA program.<sup>32/</sup> In my opinion,  
13 this is a significant omission in Mr. Reedy's review.

14 Q: Were other design process audits of the DCP quality assurance  
15 program conducted?

16 A: Yes. Both Region V of the NRC in its routine inspections and  
17 the DCP in its audit program evaluated the implementation of  
18 the design process. Similar to Mr. Reedy, Mr. Morrill of  
19 Region V acknowledged at his deposition that he had not  
20 evaluated the QA/QC significance of EOIs 1120 to 1144 in  
21 forming his opinion on the adequacy of the DCP QA program  
22 implementation.<sup>33/</sup> Further, in spite of the past history of  
23 design process discrepancies at Diablo Canyon, Region V

---

24 32. Deposition of Roger F. Reedy, September 22, 1983,  
25 pages 41, 42, 64, 65.

26 33. Deposition of Philip John Morrill, September 28, 1983,  
27 page 99. In addition, SER Supplement 18 does not address the  
potential QA/QC significance of these EOIs.

1 personnel did not significantly increase their design  
2 inspection activities at the DCP home offices during the past  
3 two years. Rather, in my judgment, a business-as-usual  
4 approach generally prevailed for design inspections.

5 Q: What do you mean by regulatory compliance review?

6 A: A regulatory compliance review provides an assessment of the  
7 quality program measures as compared to the regulatory  
8 requirements of Appendix B.

9 Q: Did the IDVP conduct a regulatory compliance review?

10 A: No. Rather, the IDVP relied upon the NRC's review of the DCP  
11 QA program as assuring that the program adequately addresses  
12 the requirements of Appendix B.

13 Q: Based on your assessment of the foregoing three measures,  
14 what is your conclusion?

15 A: The results of the IDVP design product verification, as well  
16 as its design process audits demonstrate that the ITP failed  
17 to satisfactorily execute a design quality assurance program  
18 for the design modifications developed since November 1,  
19 1981. The results further indicate that, contrary to the  
20 requirements of Criteria 1 and 2 of Appendix B, the DCP  
21 failed to establish and execute a design quality assurance  
22 program. Further, contrary to Criterion 3, the DCP's design  
23 control measures failed to assure that the Diablo Canyon  
24 design criteria were correctly translated into design  
25 documents. Indeed, the errors and potential errors set forth  
26 in Tables 5-1 and 8-1 demonstrate that the DCP QA program  
27 failed to adequately implement the required audits and

1 corrective action measures contrary to Criteria 18 and 16 of  
2 Appendix B. This conclusion inevitably follows as a result  
3 of the identified errors since Criterion 18 requires that  
4 PG&E and its design contractors perform planned and scheduled  
5 audits to verify compliance with all aspects of the quality  
6 assurance program and to determine its effectiveness.  
7 Follow-up action is intended to be initiated to address the  
8 identified discrepancies. Guidance for such follow-up action  
9 is provided by Criterion 16 which requires that appropriate  
10 corrective action be initiated to correct the identified and  
11 any similar discrepancy, to determine the cause of the  
12 discrepancy, and to preclude recurrence of further similar  
13 discrepancies.

14 Q: What do you recommend?

15 A: Given the demonstrated number and nature of the errors  
16 disclosed in the IDVP's review of a sample of the Corrective  
17 Action Program, in my judgment it is reasonable to conclude  
18 that further critical errors (Class A or B) exist in the  
19 design of the plant which can only be uncovered by a rigorous  
20 and thorough verification program. Further, the cumulative  
21 impact of the major errors (Class C) when coupled with the  
22 critical errors indicate the necessity for further  
23 verification of the post-November 1, 1981 design activities.

24 /

25 /

26 /

27 /

VIII. CONCLUSIONS

1  
2 Q: Based on the foregoing, what have you concluded?

3 A: The IDVP and the ITP have detected and corrected a number of  
4 critical errors in both the Diablo Canyon design product, and  
5 the quality assurance program measures provided to control  
6 the design process. However, in my judgment the verification  
7 program has not yet demonstrated that the design of Diablo  
8 Canyon is now in compliance with all the applicable NRC  
9 regulatory requirements and all the PG&E licensing criteria  
10 in that:

11 (a) The verification program failed to verify a  
12 suitable sample of safety-related design activities  
13 for the design services subcontracted to  
14 Westinghouse by PG&E.

15 (b) The verification program failed to systematically  
16 identify the basic causes for either the initial  
17 failure or the failure of the PG&E design quality  
18 assurance process which allowed the errors  
19 disclosed by the IDVP and ITP to occur and remain  
20 undetected. As a result, potential generic  
21 concerns were not raised, or were only partially  
22 addressed by the verification program.

23 (c) The IDVP's field verifications of a sample of the  
24 design documents resulting from the ITP's  
25 Corrective Action Program demonstrated that all  
26 configuration control errors have not been detected  
27 and corrected. Rather, the continued existence of

1 discrepancies between the "as-built" and  
2 "as-designed" configuration of the plant indicate  
3 that the corrective action measures initiated by  
4 the DCP have not been adequate to ensure that all  
5 conditions adverse to quality have been detected  
6 and corrected, and that the cause of such  
7 discrepancies is determined and action taken to  
8 preclude repetition of similar discrepancies.

9 (d) The results of IDVP's review of a sample of the  
10 post-November 1981 design activities conducted by  
11 the ITP's Corrective Action Program establish that  
12 the DCP failed to satisfactorily execute a design  
13 quality assurance program for its activities.  
14 Given the demonstrated number and nature of the  
15 design errors identified in the IDVP's review of  
16 the Corrective Action Program, in my judgment it is  
17 reasonable to conclude that further critical errors  
18 exist in the design of Diablo Canyon.

19 For the preceding reasons, the IDVP and ITP design verification  
20 efforts conducted to date have, in my judgment, failed to provide  
21 an equivalent level of assurance regarding the design of Diablo  
22 Canyon as would have been obtained by a QA/OC program executed in  
23 a timely fashion in compliance with the regulatory requirements  
24 of Appendix B.

25 /

26 /

27 /



TABLE 5-1

TABLE 5-1

DISCREPANCIES IDENTIFIED IN CORRECTIVE ACTION REVIEW

<u>DCP Analysis</u>	<u>Condition Noted by IDVP</u>	<u>EOI Issued</u>
A. <u>ITR #49 (Rev. 0)</u>		
---	The PG&E review resulted in the identification of separation and single failure concerns similar to those addressed in the initial sample. Modifications were subsequently made to provide consistency with FSAR separation commitments.	No
B. <u>ITR #54 (Rev. 1)</u>		
---	In the verification of "as-built" conditions, the IDVP found two minor instances where the as-built condition did not match the design drawings. The first case concerned the clearance of the crane wheels and guide struts versus the crane rail. Plates were modified to allow the proper clearance, and these modifications had no impact on the structural integrity. Secondly, a nonstructural plate was welded to the outer box instead of the inner box of the guide strut. This discrepancy will be resolved by the DCP for the final resolution of the operational capability of the polar crane.	No *
C. <u>ITR #55 (Rev 1)</u>		
Calc 52.15.6.1.0	The DCP used a ZPA of 1.6g for the control room slab. The revised analysis of the control room slab showed various nodes with a maximum ZPA of 2.0g.	No
----	In certain cases, the DCP considered openings which were only temporary blockouts, or neglected a minor penetration opening in a wall.	No *

\* The condition reflects a discrepancy between as-built conditions and the design documents.

<u>DCP Analysis</u>	<u>Condition Noted by IDVP</u>	<u>EOI Issued</u>
D. <u>ITR #59 (Rev. 1)</u>		
4-100, rev. 0	1. Valve modeling: The DCP neglected the weight of flange bolts which accounted for 7% of the total valve weight.	No *
	2. Stress computation: The DCP used a preliminary design pressure which was 240 psi (59%) below the value given in the subsequent DCP DCM.	No
	3. Piping geometry: A difference of 1.42 feet was noted for the length of a pipe segment.	No *
9-108, rev. 0	1. SIF applications: The DCP used 1.0 for a taper transition at the heat exchanger nozzle. The IDVP calculated the SIF to be 1.9.	Yes
	2. Interference: The DCP did not address the interference between the regenerative heat exchanger and the pipe (including interference due to insulation).	No
1-119, rev. 0	Pipe weight: A 2000 pound flow element (weight equivalent to a pipe length of about 2.7 times pipe diameter) was not included in the DCP model.	No *
2-111, rev. 0	1. Loading inputs: The DCP applied auxiliary building SAM displacements at Support 11-93SL. This support was field verified by the IDVP to be attached to the containment exterior building. Pressure effects, and thermal anchor motions at two supports were not considered in the DCP analysis.	No
	2. Piping geometry: The IDVP found that in the DCP analysis the location of Support 11-93SL differed from the as-built condition by 3 feet 2-3/16 inches.	No *

DCP AnalysisCondition Noted by IDVPEOI  
IssuedD. ITR #59(Rev. 1) (Contd)

The straight pipe between the elbow at nodes 15 and 23 was analyzed 4 feet 3 inches shorter than the dimension field verified by the IDVP.

- |                |  |      |
|----------------|--|------|
| 9-110, rev. 0  | 1. Piping geometry: A 3-foot difference was noted for elevation of Support 10-17SL between information provided by the support drawing and that used in the DCP analysis.<br><br>A 1-foot difference between IDVP field information and DCP input for one pipe segment was also noted. | No * |
|                | 2. Mass point spacing: A mass point between two horizontal supports was not modeled in the DCP analysis.   | No   |
|                | 3. Loading inputs: Two thermal load cases were not considered by the DCP.  | No   |
| 4-102, rev. 1  | Piping geometry: The DCP coded one portion of 20-inch diameter pipe 3 feet shorter and another portion of 12-inch diameter pipe 4 feet longer, than indicated by IDVP field verification.  | No * |
| 4A-100, rev. 0 | 1. Valve modeling: The DCP neglected the weight of the flanges attached to Relief Valve RV-52. This resulted in a 9% difference in the total valve weight.   | No * |

<u>DCP Analysis</u>	<u>Condition Noted by IDVP</u>	<u>EOI Issued</u>
D. <u>ITR #59(Rev. 1) (Contd)</u>		
	2. SIF application: An SIF of 1.8 was not applied at a butt weld on straight pipe near Support 57N/72R. A SIF of 2.1 was also not applied for the socket weld at a socket.	No
	3. Loading inputs: DCP pressure and temperature inputs (based on preliminary design data) were up to 59% lower than values provided in the subsequent DCM.	No
	4. Interference: Pipe deflection at Support 57N/61R (Y restraint) exceeded support clearance in the Z direction.	No
8-106, rev. 1	1. SIF application: An SIF of 1.0 was applied at the pipe flued head interface, where an SIF of 1.9 was appropriate for a taper transition joint. SIFs of 2.1 were not specified for all applicable socket welding locations.	No
	2. Interference: The DCP did not address the unintentional restraint found by the IDVP on the vertical portion of the 3/4 inch vent line.	No *
4-113, rev. 0	1. Support modeling: Support 55S/64R was modeled as a rigid + Y-directional support, whereas the IDVP field verification found it to be a gravity support.	No *
	2. Valve qualification: The gravity effect (lg) was not included in the acceleration qualification for Valve FCV-356, which has a horizontally mounted valve stem.	No



<u>DCP Analysis</u>	<u>Condition Noted by IDVP</u>	<u>EOI Issued</u>
D. <u>ITR #59(Rev. 1) (Contd)</u>		
4-113, rev. 0	3. SIF applications: SIFs applied at a 20-inch X 2-inch connection, and at a butt weld on straight pipe were up to 50% lower than SIFs calculated by the IDVP.	No
	4. Loading inputs: The design pressure (preliminary) in one of the lines was 57% lower than the subsequent DCM value.	No
2-105, rev. 0	1. SIF applications: The DCP applied an SIF of 1.0 for three branch connections. The required SIFs were determined by the IDVP to be 1.628, and 1.07.	No
	The DCP did not apply a taper transition SIF (1.9 maximum) to a flange/pipe interface.	
	SIFs for butt welds on straight pipe were also not considered by the DCP.	
	2. Loading inputs: The DCP vertical Hosgri spectra (based on preliminary data) was found to be lower than that determined alternately by the IDVP using subsequent DCM values.	No
2-120, rev. 3	Valve modeling: The weights for Valves LCV-113 and -115 were modeled 45% low for valve bodies and 8% low for valve operators. In addition, minor differences in the DCP eccentricity calculations were noted.	No *

<u>DCP Analysis</u>	<u>Condition Noted by IDVP</u>	<u>EOI Issued</u>
D. <u>ITR #59(Rev. 1) (Contd)</u>		
6-101, rev. 2	1. Interference: The pipe deflection during a thermal accident mode exceeded clearance available at Supports 40/21R and 40/22R.	No
	2. Support modeling: Support 10/44SL was modeled with an eccentricity from process pipe OD of 4.25 feet instead of 4.5 inches.	No *
	3. Load summary: The coordinate system was incorrectly shown on the flued head load summary.	No
4A-133, rev. 1	SIF modeling: The SIFs for intermediate butt welds on straight pipe were not considered.	No
4-101, rev. 1	1. Valve modeling: The DCP used a 29% lower valve weight for FCV-365 than that shown by the valve drawing. The DCP did not model valve eccentricities for 9 remote-operated valves at 11 locations. Accelerations for FCV-361 were also extracted from an incorrect location by the DCP.	No *
	2. SIF applications: The DCP ME-101 piping analysis program did not apply the taper transition SIF of 1.9 to the elbow side of the valve/elbow interface.	No
2-114, rev. 1	1. SIF application: The DCP did not apply an SIF of 1.8 to account for the butt welds on straight pipe.  The DCP applied an SIF of 3.268 at an unreinforced fabricated tee where the IDVP determined that the SIF for this tee should be 4.95.	No

<u>DCP Analysis</u>	<u>Condition Noted by IDVP</u>	<u>EOI Issued</u>
D. <u>ITR #59(Rev. 1) (Contd)</u>	The DCP also applied an SIF of 2.0 at a branch connection where the IDVP determined that the SIF should be 2.58.	
	The DCP also applied an SIF of 2.0 at a branch connection where the IDVP determined that the SIF should be 2.58.	
	2. Valve modeling: The DCP modeled 75 pounds for the weight for the 4-inch check valve. The valve drawing shows the weight to be 102 pounds.	No *
7-103, rev. 0	SIF application: The DCP did not apply socket weld SIFs consistently at socket weld elbows. Some were treated as short or long radius elbows having lower SIFs than a socket weld. The DCP also did not use a socket weld SIF of 2.1 for a swage fitting socket weld.	No
8-116, rev. 1	1. SIF applications: The DCP used an SIF of 1.5 at one 3/4-inch branch at node 32. However, the IDVP found that an SIF of 3.34 should have been used.	No
	2. Support locations: A 3-foot difference in location of one of the supports noted.	No *
8-117, rev. 2	1. Valve modeling: The DCP lumped only two-thirds of the total valve weight at the overall center of gravity for valve 9003A. The weight of the valve contents (30 pounds) was neglected.	Yes

<u>DCP Analysis</u>	<u>Condition Noted by IDVP</u>	<u>EOI Issued</u>
D. <u>ITR #59(Rev. 1) (Contd)</u>	2. SIF application: The IDVP did not apply SIFs at various locations including the flued head, branch connection and butt weld along straight pipe. The IDVP determined SIFs ranging from 1.9 to 1.5 should be used.	No
	3. Loading input: A 63% difference (as compared to the subsequent DCM value) in design pressure was noted for small portions of piping.	No
4A-111, rev. 0	1. Loading inputs: The vertical Hosgri spectra used by the DCP (based on preliminary input) was lower than that given in the DCM.  One of the thermal modes shown in the DCM was omitted from the DCP analysis (based on preliminary input).	No
	2. SIF application: The DCP applied an SIF of 1.9 at a socket weld connection instead of 2.1.	No
8-102, rev. 2	1. Valve modeling: The DCP analyzed Valve 8805B with the operator in the vertical position, but an IDVP field verification found this operator to be in the horizontal position. Also, differences were found for valve center of gravity locations for valves 8805A and 8805B and IDVP. [sic] and for operator support locations.	No *
	2. SIF application: The DCP used a SIF of 2.44 for the 3/4 inch branch on the 8 inch elbow and a SIF of 3.658 was determined by the IDVP. SIFs for two branches (3/4 inch and 2 inch), field verified by the IDVP to be attached to the 8 inch tee, were not included in the DCP analysis.	No

<u>DCP Analysis</u>	<u>Condition Noted by IDVP</u>	<u>EOI Issued</u>
D. <u>ITR #59(Rev. 1) (Contd)</u>		
12-101, rev. 0	1. SIF application: The DCP did not apply an SIF of 1.8 [sic] butt weld on straight pipe locations.	No
	2. Loading input: The DCP Hosgri spectra input (based on preliminary design data) was lower than the IDVP alternately enveloped spectra (based on subsequent DCM values).	No
E. <u>ITR #60 (Rev. ?)</u>		
<u>Calculation #</u>		
A-123 (Rev. 6)	1. In the natural frequency analysis, the tributary weight for the piping on only one side of the anchor was used.	No
	2. The minimum fillet weld size for the stanchion-to-floor plate weld was incorrectly calculated.	No
	3. The pad-to-process pipe weld was not analyzed.	No
	4. Reinforced pad stresses were not examined.	No
S-1087 (Rev. 1)	The stresses in the tee-shoe and its weld to the pipe clamp were not addressed for the friction force loading.	No
A-35 (Rev. 6)	1. The torsional stiffness of one member in the computer model was three times the correct value.	No
	2. The weld between the stanchion and the process pipe was not analyzed.	No
	3. Reinforced pad stresses were not examined.	No



<u>DCP Analysis</u>	<u>Condition Noted by IDVP</u>	<u>EOI Issued</u>
E. <u>ITR #60 (Rev. 1) (Contd)</u>		
<u>Calculation #</u>		
A-79 (rev. 1)	1. An analysis revision sheet was not included.	No
	2. The analysis load sheet did not note that the tributary pipe weight is in local coordinates whereas the remaining loads on the load sheet are in global coordinates.	No
	3. The load case 4 weld stress, which was a controlling condition, was not analyzed.	No
	4. The support frequency in the restrained direction was not addressed for the Revision 1 loads.	No
	5. The stress at the cutout in a plate member not addressed.	No
	6. Stresses in several welds were not addressed.	No
	7. The analysis did not consider the stress in the support immediately adjacent to the process pipe.	No
A-103 (rev. 5)	1. The 10 inch diameter sleeve, on which the support is mounted, was not considered in the natural frequency calculation. The IDVP considered the sleeve to be the most flexible member of the support by engineering judgement.	No
	2. The 1/4 inch groove weld between the existing lug and the process pipe was incorrectly analyzed.	No

<u>DCP Analysis</u>	<u>Condition Noted by IDVP</u>	<u>EOI Issued</u>
E. <u>ITR #60 (Rev. 1) (Contd)</u>		
<u>Calculation #</u>		
	3. The 1/4 inch fillet weld between a member and the existing lug was incorrectly analyzed. The IDVP determined that this weld stress exceeded the allowable by factoring by correct inputs.	Yes (1129)
	4. The Revision 4 sheet was not included.	No
	5. The IDVP field verification noted a weld across the top of a member attached to the process pipe. The DCP drawing did not show this weld.	No *
A-148 (rev. 4)	The DCP did not directly address the support natural frequency. However, by engineering judgement, the IDVP found that the natural frequencies were greater than the required minimum 20 Hz.	No
H-1279 (rev. 3)	1. The stress in the weld between two members [sic].	No
	2. The computer analysis does not use the maximum loads.	No
H-1040 (rev. 2)	1. The stresses in the shear lugs and the attachment welds were not addressed.	Yes (1131)
	2. A list of references was not included.	No
	3. The DCP analysis included a support drawing which showed a weld on two sides of a beam at its attachment to the existing insert. The IDVP field verification indicated an all-around weld on four sides of the beam (i.e. the DCP analysis was conservative).	No *

<u>DCP Analysis</u>	<u>Condition Noted by IDVP</u>	<u>EOI Issued</u>
E. <u>ITR #60 (Rev. 1) (Contd)</u>		
<u>Calculation #</u>		
A-22 (rev. 5)	1. The maximum combination of loads was not analyzed.	No
	2. The stress in the pipe attachment adjacent to the process pipe and in the attachment-to-process weld were not analyzed.	No
H-1052 (rev. 3)	The stresses in the shear lugs and lug-to-process-pipe weld were not specifically addressed.	No
H-1054 (rev. 3)	Member 3 (3x3x3/8 angle) was not analyzed for stress.	No
H-359 (rev. 4)	1. The length-to-thickness ratio (buckling) of a 2x2x3/8 angle member was not addressed.	No
	2. The stresses in the welded attachment and its weld to the process pipe were not addressed.	Yes (1131)
S-274 (rev. 3)	1. An analysis revision sheet was not included.	No
	2. An incorrect load was input into the computer analysis.	No
	3. Several differences were noted between the drawings and as-built conditions.	No *
	4. The analysis did not consider the cutout in a member (a built-up section of WF and angle members). Affected are the stress in the member and the frequency of the support in the X direction.	No

<u>DCP Analysis</u>	<u>Condition Noted by IDVP</u>	<u>EOI Issued</u>
E. <u>ITR #60 (Rev. 1) (Contd)</u>		
<u>Calculation #</u>		
	5. The stress in the computer model members 116 to 123, 126, 128 to 133, 141, 142 and 151 to 156 were not explicitly evaluated to AISC criteria.	No
	6. The drawing does not reference another support which is mounted on Support 85N/31R.	No *
	7. The local reduced cross section of a member was not considered in the frequency of the support and in the stress analysis of the member.	No
	8. The weld having the highest stress was not analyzed.	No
	9. The local bending of a plate was not analyzed.	No
	10. The pipe welded attachments and their welds were not addressed.	No
H-32 (rev. 5)	1. The support frequency in the unrestrained direction was not addressed.	No
	2. The support frequency in the restrained direction did not consider the flexibility of the stanchion.	No
	3. The bending and axial stresses were interchanged in the stress interaction equation.	No
	4. The Civil Verification Transmittal sheet (notifies the civil group of support loads > 500 pounds) was not included.	No

<u>DCP Analysis</u>	<u>Condition Noted by IDVP</u>	<u>EOI Issued</u>
E. <u>ITR #60 (Rev. 1) (Contd)</u>		
<u>Calculation #</u>		
	5. The revision sheet was not included.	No
	6. The IDVP field verification noted a 1/4 inch plate between the baseplate and Member 9 which was not shown on the support drawing (no impact).	No *
S-245 (rev. 5)	1. There was insufficient documentation to verify the displacement value on which the frequency was based.	No
	2. The frequency analysis did not consider all the flexible members in the support.	No
	3. Incorrect acceleration values were used in the analysis.	No
	4. The pipe clamp was not stress analyzed.	No
	5. The analysis of a weld did not consider one moment.	No
	6. The stresses in the shear lugs and their welds were not addressed.	No
MP-398 (rev. 2)	1. The stress of Member B (1/4 inch plate) was not addressed.	No
	2. The torsional stress calculation of Member 7 (3x3x3/8 angle) did not use the member thickness.	No
	3. The analysis incorrectly computed a shear area for a clevis.	No
	4. The analysis did not consistently incorporate the evaluation of increased design loads.	No



<u>DCP Analysis</u>	<u>Condition Noted by IDVP</u>	<u>EOI Issued</u>
E. <u>ITR #60 (Rev. 1) (Contd)</u>		
<u>Calculation #</u>		
MP-155 (rev. 3)	The maximum stress was reported as approximately half the maximum stress found by the IDVP in the STRUDL analysis.	No
MP-306 (rev. 2)	A moment load was omitted in the analysis of the critical weld.	No
MP-249 (rev. 2)	1. The weld stress analysis used incorrect values for the MX load and for the section modulus.	No
	2. Certain member and weld stresses for Load Cases 1 and 2 were evaluated against incorrect allowables (i.e., based on Load Cases 3 and 4).	No
	3. The IDVP field verification noted that one of the four restraints comprising this support was a small box frame bilateral rather than a tee-shoe and clamp assembly as shown on the DCP support drawing.	No *
MP-983 (rev. 1)	1. Loads provided by the applicable piping analyses did not appear, in all cases, to be those used in the support analyses.	No
	2. Determination of loads at overlap supports was not addressed.	No
	3. There were some discrepancies in the member properties used in the hand calculations (e.g., torsion constant for Member 52).	No
	4. Discrepancies were noted in some weld section properties and in some member properties (e.g., for the majority of the frame, the properties used were for M4x13 instead of W4X13).	No

<u>DCP Analysis</u>	<u>Condition Noted by IDVP</u>	<u>EOI Issued</u>
E. <u>ITR #60 (Rev. 1) (Contd)</u>		
<u>Calculation #</u>		
M-178 (rev. 2)	1. The analysis used a shear area of the full channel in calculating the stress in the channel, rather than using just the web area consistent with each direction.	No
	2. Welded attachments (lugs) and their welds to the process pipe were not evaluated.	No
	3. The analysis erroneously calculated and compared the frequency in the restrained direction to an incorrect value.	Yes (1139)
7-301 (rev. 0)	1 Preliminary thermal operating modes were used by DCP in Revision 0. Revision of this analysis used values from the subsequent DCM.	No
	2. An SIF of 1.3 (instead of 2.1) was applied at two socket weld locations without appropriate DCP field verification documentation. Also, at one location, an SIF = 1.0 (instead of 2.1) was applied for a half coupling.	No
	3. One piping geometry modeling difference (location of data point 40A) between the computer model and the walkdown isometric was identified.	No *
8-305 (rev. 1)	From the IDVP field verification, unintentional restraints were not shown on the PGandE isometric.	No *

<u>DCP Analysis</u>	<u>Condition Noted by IDVP</u>	<u>EOI Issued</u>
E. <u>ITR #60 (Rev. 1) (Contd)</u>		
<u>Calculation #</u>		
8-306 (rev. 3)	1. In several cases, pipe geometry modeling differences exceeded DCP tolerances.	No *
	2. The weight of one valve was input as 25.7 lb instead of 50.7 lb.	No *
8-310 (rev. 2)	1. One pipe length, as shown on the DCP walkdown isometric was modeled exceeding the DCP tolerance.	No *
	2. Unintentional restraints, as shown on the DCP walkdown isometric and by IDVP field verification, were not explicitly addressed in the analysis.	No *
	3. Preliminary thermal operating modes were used by DCP in Revision 2. The DCP compared the preliminary data against values in the subsequent DCM and judged these acceptable.	No
8-311 (rev. 4)	1. Differences were noted between the documentation package (e.g. stress isometric) and the computer analysis. These documentation differences were resolved in Revision 5 of this analysis.	No
	2. One three-way support is modeled as a two-way. The analysis did not address the modification.	No *
9-304 (rev. 1)	Thermal operating modes and large bore piping displacements (SAM/TAM) used by the DCP in the analysis were listed as preliminary. Revision of this analysis used values from the subsequent DCM.	No

<u>DCP Analysis</u>	<u>Condition Noted by IDVP</u>	<u>EOI Issued</u>
E. <u>ITR #60 (Rev. 1) (Contd)</u>		
<u>Calculation #</u>		
9-307 (rev. 1)	The weight of a valve and a branch in the overlapped region were not modeled in the analysis.	No *
10-301 (rev. 2)	<ol style="list-style-type: none"> <li>1. Thermal operating modes, large bore displacements (SAM/TAM) and containment dilation movements were based on preliminary data. Revision of this analysis used values from subsequent DCMs and other controlled documents.</li> <li>2. The analysis did not address valve operator support requirements. Revision of this analysis was performed to address this subsequent DCP procedural requirement.</li> <li>3. At four locations, an SIF = 1.0 (instead of 2.1) was specified for couplings.</li> <li>4. The weight of insulation for a portion of the pipe was not considered in the analysis.</li> </ol>	No
3-303H (rev. 3)	<ol style="list-style-type: none"> <li>1. It was noted that the walkdown isometric and analysis considered the line to be insulated, whereas the IDVP found it to be uninsulated.</li> <li>2. A short segment of pipe up to the code break valve was 431 degrees Fahrenheit, which exceeded the recommended span rule temperature range. The DCP analysis adequately considered these temperature effects.</li> <li>3. The effects of X, Y, and Z displacements were considered separately rather than considering the resultant displacement perpendicular to the pipe span for pipe flexibility evaluation.</li> </ol>	No *

<u>DCP Analysis</u>	<u>Condition Noted by DVP</u>	<u>EOI Issued</u>
E. <u>ITR #60 (Rev. 1) (Contd)</u>		
<u>Calculation #</u>		
	4. Components such as valves and elbows were considered to have the same flexibility as the pipe for the thermal flexibility evaluation of a short run of pipe.	No
	5. The response spectral acceleration of auxiliary building flexible slabs was not considered in the analysis.	No
	6. The seismic stress acceptability was not specifically documented in the analysis.	No
6-301H (rev. 3)	1. A short segment of pipe up to the code break valve was 365 degrees Fahrenheit, which exceeded the recommended span rule temperature range. The DCP analysis adequately considered these temperature effects.	No
	2. The valve weight (one case) shown on the valve drawing was greater than that used in the analysis.	No *
	3. The equivalent weight used to determine a seismic span containing concentrated weights was incorrectly calculated.	No
	4. Support loads due to SAM/TAM for one support were not summarized on the small bore hanger review sheet.	No
	5. The effects of an anchor in the non-seismic portion of the piping were not evaluated for pipe flexibility considerations. (See EOI 1142 below.)	Yes
9-327H (rev. 2)	The analysis underestimated the design loads and effective weight at one support.	No *



<u>DCP Analysis</u>	<u>Condition Noted by IDVP</u>	<u>EOI Issued</u>
E. <u>ITR #60 (Rev. 1) (Contd)</u>		
<u>Calculation #</u>		
19-307H (rev. 2)	1. A portion of the pipe was 280 degrees Fahrenheit which exceeded the recommended span rule temperature range. However, the temperature used in the DCP analysis for this piping was 120 degrees Fahrenheit.	No
	2. Documentation was not provided for the active valve acceleration qualification.	No
	3. Support loads due to SAM/TAM for one support were not summarized on the small bore hanger review sheet.	No
F. <u>ITR #63 (Rev. 1)</u>		
<u>Analysis #</u>		
HV-59	The IDVP field verified that only three of the five analyzed supports existed in the field (-05, -07 and -13). Support 07 was analyzed as the worst case support with a duct tributary length of 15.75 feet.	No *
HV-88	The IDVP review of HV-88 resulted in the issuance of EOI 1143 citing the misapplication of seismic coefficients.	Yes
HV-104	Ceiling connection detail for support 59357-38 shows a gap under a ceiling mounting plate. The methodology used to analyze the plate did not adequately account for the gap.	No *
HV-116	DCP sketches and as-built data did not correlate with the support analysis. In addition, DCNs for modifications were omitted from the documentation package.	No *

<u>DCP Analysis</u>	<u>Condition Noted by IDVP</u>	<u>EOI Issued</u>
F. <u>ITR #63 (Rev. 1) (Contd)</u>		
<u>Analysis #</u>		
HV-119	Analysis did not include weight of insulation in determining duct frequency.	No
HV-81 HV-86 HV-87 HV-96	EOI 1134 was issued as a result of the IDVP review of the DCP Corrective Action Program. The DCP used an approximate procedure to determine a response frequency based on the Rayleigh-Ritz method as performed by the ICES STRUDL II computer code. This procedure was used for the seismic analysis of HVAC ducts and supports.  The EOI was issued because, in some cases, frequencies reported by the DCP were significantly different from those alternately calculated by the IDVP. This difference occurred because the DCP frequencies did not always correspond to the first mode natural frequency.	Yes
S-80B	1. The design analysis did not consider the support deadweight.	No
	2. The design analysis did not explicitly evaluate column stability.	No
S-262	One of the as-built supports had a member length slightly longer than the length used.	No *
S-314	The dead analysis did not consider the support deadweight.	No
S-356	1. The generic calculation was not based on maximum generic conduit weight as required by DCM C-15, Revision 3.	No
	2. Stresses at key support connections were not evaluated.	No
	3. The analysis did not account for the manufacturer's allowables in the analysis of Unistrut.	NO

<u>DCP Analysis</u>	<u>Condition Noted by IDVP</u>	<u>EOI Issued</u>
F. <u>ITR #63 (Rev. 1) (Contd)</u>		
<u>Analysis #</u>		
S-562	Analysis neglected deadweight of the support structure and did not apply peak accelerations. However, the DCP analysis used twice the approximate weight of the attached box.	No
S-623	The DCP computer model did not fully account for proper boundary conditions and for all restraint reactions.	No
(Field Verification of Corrective Action)	The IDVP field verification determined that a conduit clamp modification for support CSR-127-6-471 had been incorrectly implemented. DCN DCT-EC-3604, Revision 0, specifies changing a conduit clamp on conduit K7218 based on Analysis ACSR-127-T1. The IDVP field documentation (Reference 8A) shows the new clamp to be on conduit K8375, which is adjacent to conduit K7218.	No *
ITS-2 (rev. 1)	The IDVP reviewed ITS-2 using a written checklist. The results of the review indicate that ITS-2 does not follow the established DCP analysis methodology.	No
ITS-4 (rev. 1)	1. Incomplete support weight.	No
	2. Unreferenced seismic acceleration coefficients are lower than the latest spectra acceleration values.	No
	3. Analytical methods which may have provided unconservative results.	No
ITS-5 (rev. 1)	Of the seven support analyses, one support used an assumed member size and section property which did not agree with the as-built member size.	Yes * (1123)

<u>DCP Analysis</u>	<u>Condition Noted by IDVP</u>	<u>EOI Issued</u>
F. <u>ITR #63 (Rev. 1) (Contd)</u>		
<u>Analysis #</u>		
ITS-6 (rev. 1)	1. One support type did conform to DCP as-built information.	No *
	2. Two of the supports analyzed no longer exist.	No
	3. Four of the supports carried loads greater than those used in the DCP analysis.	No *
	4. One support could not be located in the field.	No *
(Field Verification)	Four of sixteen supports were found to carry loads greater than those documented by the DCP.	No *
U-131	The DCP effective length (13.1 inches) differs from the IDVP alternate calculation (28 inches).	No
U-192	The analysis assumed that the closed loop double U-bolt was fixed at midlength. This resulted in an effective gap which led to a pipe rupture load that exceeded the established NSC allowable.	No
U-313	The DCP rod effective length (48 inches) differs from the IDVP alternate calculation (91 inches).	No
U-355	The DCP U-bolt effective length (103 inches) differs from the IDVP alternate calculation (87 inches).	No

<u>DCP Analysis</u>	<u>Condition Noted by IDVP</u>	<u>EOI Issued</u>
F. <u>ITR #63 (Rev. 1) (Contd)</u>		
<u>Analysis #</u>		
(DCP test program for U-bolt connectors)	The DCP test program is responsive to the IDVP QA finding noted in ITR #42. Based on negative test results, several design modifications have been planned and implemented. In particular, the nuts and couplers are being replaced with split wedge designs. During the connector testing, the DCP noted a concern with the ductility of the U-bolts and rod beams. DCP Open Item 42 has been issued to track this ongoing work.	No
S-20	1. The adequacy of the baseplate was not explicitly addressed in the analysis. 2. A dynamic impact factor of 1.8 was not applied.	No
S-30	1. The stresses in one key member were not evaluated. 2. The adequacy of the base plate connections was not evaluated for plastic moment transmitted through coped flange joints.	No
S-130	The analysis did not explicitly apply a 1.8 dynamic impact factor or evaluate the rock bolts.	No
S-150	1. The concrete shear cone area was underestimated by 50% in the design analysis. 2. The adequacy of the base plate connections was not evaluated for plastic moment transmitted through coped flange joints.	No



<u>DCP Analysis</u>	<u>Condition Noted by IDVP</u>	<u>EOI Issued</u>
F. <u>ITR #63 (Rev. 1) (Contd)</u>		
<u>Analysis #</u>		
S-240	1. The design analysis incorrectly calculated the allowable values for the bearing plate.	No
	2. The DCP incorrectly calculated the fundamental frequency in the plane normal to the frame.	No
	3. The capacities of the through bolts were not evaluated.	No
S-260	1. The design analysis incorrectly analyzes the weld stress in a column plate.	No
	2. Rock bolts were evaluated using a dynamic impact factor of 1.25 rather than 1.8.	No
	3. The coupled U-bolt/substructure analysis results were incorrectly evaluated.	No
S-329	1. The endmost line loads were modeled incorrectly in the analysis.	No
	2. The design analysis does not evaluate the anchor under rupture loads from each of the 5 pipe lines and all 6 load components of a single pipe rupture.	No
S-331	1. Two of the bolts in the four bolt plate joint between two column members had been cut out to prevent pipe movement interference. The impact of the reduced section was not evaluated.	No *
	2. Bolts connecting beam base plate to embedded plate were not evaluated for shear stresses developed between the plates.	

TABLE 8-1

TABLE 8-1

ERRORS IDENTIFIED IN DESIGN PRODUCT REVIEW  
(Design Modifications Since November 1, 1981)

<u>Description of Error</u>	<u>Appendix B Criteria *</u>	<u>EOI Reference</u>	<u>Error Class</u>
1. Differences disclosed between "as analyzed" and "as-built" bolt sizes.	3,6,10,16	EOI 1120 EOI 1121	Error C
2. Differences disclosed between "as-built" and "as-analyzed" instrument tubing support.	3,6,10,16	EOI 1123	Error C
3. Design analysis finite element model of the control room slab used to generate Hosgri spectra does not agree with the field verified location of the supporting wall.	3,6,10,16	EOI 1124	Error B
4. Revision 1 of the HVAC compressor seismic calculation used incorrect and unconservative spectra.	3,6,16	EOI 1125	Error C
5. DCP used improper stress intensification factors (SIF).	3,6,16	EOI 1126, EOI 1138	Combine w/ EOI 1098 (Error A/B)
6. Deficiencies in DCP reanalyses of station battery racks regarding bolt diameter and resolved shear force.	3,6,10,16	EOI 1128	Error C

---

\* The designation of Appendix B criteria relevant to the identified deficiencies is intended to highlight the major QA/QC criteria violated and, as such, is not intended to be an exhaustive list. The preceding limitation is necessary also because of the high degree of interrelationship between a number of the criteria of Appendix B.

Description of Error	Appendix B Criteria *	EOI Reference	Error Class
7. Errors in the design reanalyses for large bore pipe support 565/3A.	3,6,16	EOI 1129	Error C
8. Reanalyses of large bore pipe supports not evaluated as required by the DCP procedure.	3,6,16	EOI 1131	Deviation
9. Failure to perform an evaluation of Auxiliary Building slabs for in-plane loadings contrary to the PG&E Final Report dated May 18, 1983.	3,6,16	EOI 1132	Combine w/ EOI 1097 (Error A/B)
10. Incorrect valve modeling in DCP seismic reanalyses.	3,6,16	EOI 1133, EOI 1135, EOI 1137	Combine w/ EOI 1098 (Error A/B)
11. Use of incorrect bolt allowable stress in the DCP reanalysis.	3,6,16	EOI 1136	Error C
12. Error in the design analysis calculation of frequency of a small bore pipe support.	3,6,16	EOI 1139	Error C
13. DCP analysis failed to examine the discharge nozzle flanged joint. As-built configuration does not conform to PG&E piping specification.	3,6,10,16	EOI 1140	Error C
14. DCP failed to identify all high energy lines inside and outside containment.	3,6,16	EOI 1141	Combined w/ EOI 1098 (Error A/B)
15. Pipe support loads due to the effects of various loading combinations not considered in the design analysis contrary to the DCP design criteria procedure.	3,6,16	EOI 1142	Error C

<u>Description of Error</u>	<u>Appendix B Criteria *</u>	<u>EOI Reference</u>	<u>Error Class</u>
16. DCP analysis does not correctly consider the effect of the revised vertical and horizontal Hosgri spectra.	3,6,16	EOI 1143	Error C
17. Design analyses performed to generically qualify vents and drains may not be conservative.	3,6,16	EOI 1144	Error C
18. Hosgri design response spectra for the containment interior structure developed by DCP does not envelope raw spectra developed by the IDVP.	3,6,16	EOI 3009	Error C