B&W ADVANCED TECHNOLOGY LESSON PLAN							
Lesson No. 506-42	tle: OCONE	e: OCONEE-2 TUBE LEAK EVENT					
Written by: G. A. Van Sickle		Approve	ed by:	Ell	Date: 11/15/91		
	1.0 Training Aids 1.1 Transparencies for B&W Advanced Manual Chapter 31						
	 2.0 Reference Material 2.1 B&W Advanced Manual - Chapter 31 2.2 B&W EOP Manual - Chapter 6 2.3 INPO 82-030, "Analysis of Steam Generator Tube Rupture Events at Oconee and Ginna," November 1982 						
	 3.0 Objectives 3.1 List the symptoms of a steam generator tube leak. 3.2 Describe the actions that should be taken if the tube leakage exceeds technical specification limits. 3.3 List three actions that can be taken to minimize offsite releases during steam generator tube leakage events. 						
Sequence of Events Attach-	4.0	Presentation	on - Event C	Chronology			
ment	4.1 Initiation of the Leak 4.1.1 Initial conditions: Power escalation following mid-cycle outage.						
Objective 1	4.1.2 Evidence of leak: a. High condenser off-gas monitor reading.						
Objective 3	 b. High activity from air ejector grab samples. 4.1.3 "Control of Secondary Contamination" implemented: a. Turbine building and Powdex (condensate polisher) sum pumps secured. b.Potentially contaminated drains rerouted from turbine 						
Objective 1		bu 4.1.4 Mor a. O b. H	ilding sump e leak evide ff-gas moni	ding sump to hotwell pump sump. leak evidence: Gegas monitor reading off-scale high. gh reading on B steam line radiation monitor. ak calculated at 25 gpm from air ejector grab sample.			
Objective 2	4	heca	trolled shut	down executed; S makeup maintair	GTR procedure not entered ned PZR level.		
Objective 3		4.2.2 Stea	m pressure	was maintained l	below MSSV set pressure.		

B&W ADVANCED TECHNOLOGY LESSON PLAN							
Lesson No. 506-42	Title:	: OCONEE-2 TUBE LEAK EVENT					
Written by: G. A. Van Sickle		Approved by:		Date:			
	 4.2.3 B OTSG was isolated. (Note: No MSIV's at Oconee; closure of turbine stop valves and B-side TBV's isolated the OTSG on the steam side.) 4.3 Plant Cooldown 4.3.1 Cooldown on A OTSG. 						
Figure 31-1 Figure 31-2	4.3.2 HPI initiated to make up for leakage, cooldown "shrink." 4.3.3 B OTSG pressure was saturation pressure for T _c . 4.3.4 Steam line temperatures remained higher than OTSG saturation temperatures, reflecting slow cooling of steam line						
Figure 31-1	metal. 4.3.5 OTSG A level decreased to low-level limits; OTSG B level increased with leakage.						
Objective 3	 4.3.6 OTSG B was periodically drained to hotwell through hot blowdown lines; this prevented filling main steam lines but contributed to hotwell and eventual turbine building sump contamination. 4.3.7 One DHR hot-leg suction isolation valve failed to open electrically from control room. Valve eventually opened several hrs. later. During delay, RCS pressure for RCP operation was maintained, keeping leak driving force high. 4.3.8 Event terminated with pumpdown of RCS loops. 						
	4	 4.4 Turbine Building Flooding and Decontamination 4.4.1 Condensate storage tank (CST) overflowed to turbine building sump twice during event. a. Overflows were largely due to condensate surge volume arrangement. Upper surge tanks (UST's) are kept nearly full for AFW capacity requirement. UST's overflow to CST, which overflows to turbine building sump. b. Condensate system realignments resulted in surge volume upsets. Since OTSG B was being drained to the hotwell this caused overflow of contaminated water to the turbine building sump. 4.4.2 FWP seal injection sump overflowed to turbine building sump while seal injection sump pumps were OOS. 4.4.3 Decontamination involved processing of 2.5 million gallon of water. 					