APPENDIX B

ADDITIONAL CONDITIONS

FACILITY OPERATING LICENSE NO. DPR-25

The licensee shall comply with the following conditions on the schedules noted below:

Amendment Number	Additional Condition	Implementation Date
152	The licensee shall complete the evaluation of the torus attached piping.	Prior to Unit 3 returning to Mode 3 from refueling outage D3R14.
152	The EOPs shall be changed to alert operator to NPSH concerns and to make containment spray operation consistent with the overpressure requirements for NPSH.	Shall be implemented within 30 days after issuance of Amendment No. 152.
155	This amendment authorizes the licensee to incorporate in the Updated Final Safety Analysis Report (UFSAR), the description of the Reactor Coolant System design pressure, temperature and volume that was removed from Technical Specification Section 5.4, and evaluated in a safety evaluation dated June 12, 1997.	30 days from the date of issuance of Amendment No. 155.
158	The licensee shall review the Dresden Operation Annunciator and General Abnormal Conditions Procedures and revise them as required to ensure operator action is taken in a timely manner to limit occupational doses and environmental releases.	60 days from the date of issuance of Amendment No. 158.
158	The licensee shall change the setpoints for the Main Steamline Radiation Monitor and Offgas System Radiation Monitor alarms to 1.5 times the normal full power N-16 background (with hydrogen addition) dose rates.	60 days from the date of issuance of Amendment No. 158.