Batching, Mixing, and Transporting Concrete



Objectives

- Standards
- Batching
- Mixing
- Transporting

ASTM C94/C94M

Standard Specification for Ready-Mixed Concrete

- Materials specifications
- Ordering information
- Slump tolerances
- Measuring tolerances
- Mixer/Agitator requirements
- Delivery methods
- Testing methods



ASTM C685/C685M

Standard Specification for Concrete Made by Volumetric Batching and Continuous Mixing

- Materials specifications
- Ordering information
- Slump tolerances
- Measuring tolerances
- Mixing mechanism
- Delivery methods
- Testing methods




ACI 304R

Guide for Measuring, Mixing, Transporting, and Placing Concrete

- Control, handling, and storage of materials
- Measurement and batching
- Mixing and transporting
- Placing
- Volumetric batching

Batching



- Process of measuring concrete mixture ingredients by either mass or volume
- Most specifications require batching by mass

Batching by Volume

- ASTM C685
- Yield checks
- Proportioning checks




Tolerances for batching by volume:

- Cement, mass% = 0 +4
- Fine aggregate, mass% = ±2
- Coarse aggregate, mass% = ±2
- Admixtures, mass or volume% = ±3
- Water, mass or volume% = ±1

ASTM C94

Batching plant precision control
 discharge operation

Plant scales accurate to ±0.15%
 total capacity or
 0.4% net applied
 load



Cementitious materials:

 Measured separately or combined sequentially



- Cement first
- Tolerance at 30% or greater of full scale capacity
 ±1% required mass
- Tolerance for loads smaller 30% of scale capacity- 0-+4% required mass

Aggregate:



- Can be measured individually or combined
- Tolerances
 - Individual loads ±2% of required mass
 - Cumulative loads
 - 30% or more of scale capacity ±1% of required mass after each successive weighing
 - colless than 30% of scale capacity the lesser of ±0.3% of scale capacity or ±3% of required mass

Water:

- Tolerance ±1% by mass or volume
- Ice must be measured by mass
- Wash water remaining in truck mixer drums must be accurately measured
- Total water tolerance ±3% of the specified total amount



Admixtures:



- Powdered admixtures mass
- Liquid admixtures mass or volume
- Tolerance greater of:
 - ◆ ±3% of total amount required
 - ±100% dosage per 50kg (100lbs) of cement

Inspecting Batch Plants

ACI 311.5

- Project specification compliance
- Storage standards compliance
- Materials testing standards compliance
- Truck operating conditions
- Equipment calibration
- Batch ticket verification



Mixing and Transporting Concrete

- Ordering concrete
- Ready mixed concrete
- Mobile batcher mixed concrete
- Remixing concrete



ASTM C94/C685

Purchaser specifies:

- Sizes of coarse aggregate
- Slump at point of delivery
- Air content at point of delivery
- One of three options for remaining parameters

ASTM C94/C685

Option A—performance based:

Purchaser specifies:

Compressive strength

Concrete producer selects mix proportions.

ASTM C94/C685

Option B—prescription based:

Purchaser specifies mixture proportions including:

- Cement content
- Water content
- Admixture type and content

ASTM C94/C685

Option C—mixed option:

Purchaser specifies:

- Compressive strength
- Cement content
- Admixture type and content

Concrete producer selects mix proportions.

Prescription to Performance (P2P)

- Move away from prescription specifications
- Move towards performance specifications
- Focus final product performance

P2P - Advantages

- More efficient process
- Encourages cooperation
- Improved consistency

Ready Mixed Concrete

- Central-mixed concrete
- Shrink-mixed concrete
- Truck-mixed concrete




Central-mixed Concrete

- Mixed completely in a stationary mixer
- Delivered in
 - a truck agitator
 - a truck mixer operating at agitating speed
 - a non-agitating truck



Central Mix Plant



Stationary Mixers



- Stationary Mixers
 - Onsite or central mix ready mixed concrete plant
 - Used for complete or shrink mixing
- Mixer Types up to 9 m³
 - Tilting or non-tilting drum
 - Open top revolving blade or paddle

Ready Mixed Concrete

Shrink-mixed Concrete

 Partial mixing in stationary mixer and completed in truck mixer

Stationary mixing time should be minimum

Performance tests same as central-mixed concrete

Ready Mixed Concrete

Truck-mixed Concrete



- Mixed completely in a truck mixer
- 70 to 100 mixing revolutions, mixing speed
 6-18 rpm
- Agitating speed = 2-6 rpm
- Discharge before 1½ hours or 300 revolutions

Mixer Trucks




Used for: pavements, structures, and buildings – distances must allow discharge of concrete within 1½ hours

Advantages: central mixing plant not needed, discharge is well controlled

Watch for: Timing of deliveries should suit job organization. Concrete crew and equipment must be ready onsite to handle concrete. Control of quality is not as good as with central mixing.

Mixer Trucks





Rear Discharge

Front Discharge

Agitator Trucks



Used for: Transporting concrete for all uses. Haul distances must allow discharge of concrete within 1½ hours.

Advantages: Operate usually from central mixing plants.

Watch for: Timing of deliveries should suit job organization. Concrete crew and equipment must be ready onsite to handle concrete.

Non-agitating Truck



Used for: Transport concrete on short hauls over smooth roadways.

Advantages: Cost of nonagitating equipment is lower than that of truck agitators or mixers.

Watch for: Slump should be limited. Possibility of segregation. Height upon discharge is needed.

Mobile Batcher Mixed Concrete

- Auger-type mixer
- Mixing rate determined by manufacturer
- Slump tolerances ~ ±40mm (1.5 in) depending on specified slump

Mobile Batcher Mixed Concrete Uniformity

Requirements for Within-Batch Uniformity of

	Comorato	
	Concrete	Range of 2 Samples
,	Air content, %	1.0
,	Air free density	16 kg/m³ (1.0 lb/ft³)
,	Slump	
,	Avg. <100mm (4 in)	25 mm (1 in)
,	Avg. >100mm (4 in)	40 mm (1.5 in)
,	Coarse aggregate content, % mass concrete	6.0
,	7-day strength, % of average	7.5

Mobile Batcher Mixer Truck

Used for: Intermittent production of concrete at jobsite, or small quantities.


Advantages: Combined materials transporter and batching and mixing system. One-man operation.




Watch for: Good preventive maintenance program.

Materials must be identical to those in original mix design.

Truck Manufacturers Bureaus







Remixing Concrete

ASTM C94

Water may be added at jobsite provided:

- Spec. w/c-ratio is not exceeded
- Measured slump less than specified
- Mixing time or drum revolutions not exceeded
- Concrete is remixed
 - min. 30 rev. at mixing speed
 - until uniformity is within limits

Transporting Concrete

Watch out for:

- Delays
 - Labor force management
 - Equipment selection
 - Route planning

- Early stiffening
 - Flash/False set
 - Accelerated hydration



Transporting Concrete

Watch out for:

Drying out

- Hot and dry weather
- Low W/CM
- Use of silica fume or admixtures that affect blowater

Segregation

- Cohesive mixture
- Placing method and rate



